



Civil Utilities Planning Report

Cloonmore Regeneration LRD, Tralee, Co. Kerry

On behalf of Tulfarris CG Ltd.

August 2023

Contents

1. Introduction 3

2. Site Location 3

3. Water Supply Proposals 4

4. Foul Water 5

5. Storm Water 5

5.1 Design Parameters 6

5.2 SUDS Measures 6

5.2.1 Bioretention Systems/Rain Gardens 7

5.2.2 Tree Pits 7

5.2.3 Attenuation Storage Tanks 8

5.3 BRE 365 Infiltration Testing 8

6. Public Lighting 9

7. Telecom and other Electrical services 9

8. Road Geometry 10

Figures

Figure 2-1: Aerial Image of Site 33

Figure 2-2: Water courses in vicinity of the site (EPA Maps) 44

Figure 5-1: Storm Water Design Parameters 36

Figure 5-2: Raingarden with infiltration and overflow 37

Figure 5-3: Tree Pit 37

Figure 5-4: Attenuation Storage Tanks 38

Figure 5-5: Infiltration Testing 39

Appendices

Appendix A - Confirmation of Feasibility

Appendix B - Proposed Storm, Foul and Watermain Layout

Appendix C - Water Mains and Foul Calculations for the site

Appendix D - Maintenance Plan and Schedule for Storm Drainage Infrastructure

Appendix E - Storm Water Design Report

Appendix F - Foul Water Design Report

Appendix G - Infiltration Testing

Appendix H - Proposed Site Lighting Layout

Appendix I - EV Charging Information

Appendix J - Swept Path Analysis

Project No.	Doc. No.	Rev.	Date	Prepared By	Checked By	Approved By	Status
23824	6009	A	25/08/2023	G. Fitzgerald S Moriarty	IB	IB	Final

MWP, Engineering and Environmental Consultants
Address: Park House, Bessboro Road, Blackrock, Cork, T12 X251
www.mwp.ie



1. Introduction

Malachy Walsh and Partners (MWP) were commissioned by Tulfarris CG Ltd., to provide a design for the civil utilities serving the site namely, stormwater, foul water, water supply and public lighting in connection with a planning application for proposed large residential development at Cloonmore Regeneration LRD, Tralee, Co. Kerry. This report outlines the engineering design proposals for the elements described above relating to the planning application. The proposed development consists of 147 residential units (129 apartments and 18 Townhouses), new vehicular and pedestrian access from the newly developed Cloonmore Avenue, pedestrian and cycle access only from Boherbee road, shared open spaces, landscaping, drainage and all associated site development works. The design has been completed so that the current phase can function independently as well as easily integrating with Phase 2 of the Ballymullen Clash Link Road with a potential future access to the development at the southeast subject to agreement with Kerry County Council.

2. Site Location

The site is located to the southeast of Austin Stack's Park and Boherbee roundabout. University Hospital Kerry is located to the southeast of the site. See Figure 2-1 below for an aerial image of the site.



Figure 2-1: Aerial Image of Site

The site is relatively flat, levels on the site vary 8.116mOD on the east to 7.020mOD (AOD Above Ordnance Datum) on the west with the site slightly falling from east to west. The proposed site is currently part greenfield and

brownfield. The site area is approximately 1.55ha. The EPA records the presence of The Big River to the west of the site and the River Lee to the south of the site as shown in Figure 2-2. MWP were appointed to prepare a Civil Utilities Report with respect to this development.




Figure 2-2: Water courses in vicinity of the site (EPA Maps)

3. Water Supply Proposals

A plan of the existing services present in the area is provided in the Confirmation of Feasibility (COF) shown in Appendix A. There is an existing connection to the site, but this is proposed to be replaced by the Works. There is an existing 150mm diameter uPVC watermain to the North of the site on the R875 Boherbee Road.

A Pre-connection enquiry was submitted to Irish Water for 145 residential units on the site. IW advised that connection is feasible subject to minor upgrades as per the COF attached in the Appendix A.

It is proposed to connect the proposed development to the existing watermain in the public road via a 150mm diameter connection. This connection will serve the residential units. A 150mm watermain is designed along the spine of the development. Branches of 110mm will serve routes with less than 100 residential units.

Refer to calculations in Appendix C for further information on predicted flow rates based on the Code of Practice by Irish Water. The proposed layout is shown in Appendix B.

4. Foul Water

The proposed development will be served by a gravity system which drains into the existing foul sewer network inside the western boundary of the site as per drawing 23824-MWP-00-00-DR-C-2100, attached in Appendix B.

Irish Water advised in their confirmation of feasibility for a 145-unit proposal that the connection is “feasible subject to upgrades (possibly)”. No Upgrades identified at present, DAP for Tralee Town will be available early 2024 which may identify upgrades to the network.”

A plan of the existing Irish Water services present in the area is provided in the COF attached in Appendix A. A 750mm diameter combined sewer is shown to pass through the site, the location of this sewer and manhole was confirmed on the topographical survey. A connection to this sewer will be made at a single point as shown. All details and designs will be in accordance with Irish Water Codes of Practice. A 5.0m wayleave is shown over this sewer along the full extents of the site. This sewer has influenced the design.

Calculations with predicted flow rates are shown in Appendix C using the Irish Water Code of Practice. The full Foul Water Design Report is attached in Appendix F.

5. Storm Water

As noted, there is an existing 750mm combined sewer running within the site boundary, and a 375mm pipe located along the R875 road to the north. Irish Water have stated in the COF attached in Appendix A that stormwater will not be accepted into this system from the proposed development. There are no immediate watercourses surrounding the site for discharge of storm water. Previous infiltration tests from December 2019 and recent testing in June 2023 show that the site has infiltration capacity. The infiltration testing results are attached in Appendix G.

Site investigations indicate subsoil's consist of sandy gravels to depth. These sandy gravels have been tested in accordance with BRE365, these tests indicate a high permeability K value up to 1.8×10^{-3} m/s. The results show good infiltration media indicating that infiltration on site is a viable method of removing surface water from the development. The infiltration testing is detailed in section 5.3.

A SuDS system with greater at source water quality characteristics is considered to be a more sustainable method of storm water control on this site. The permeability of the soil allows full infiltration to ground water. It is proposed to install a new storm water sewer system within the development. The design has been completed taking cognizance of the Greater Dublin Regional Code of Practice for Drainage Works (GDSDS) and the CIRIA SUDS manual 2015.

The surface water drainage system will incorporate all hardstand areas including rainwater from the roofs of each of the apartment blocks and houses which will be discharged into a central carrier pipe located down the central spine corridor. Storm water runoff along the carriageway will be directed to a mixture of bioretention systems, tree pits and direct gully discharge. The system is designed to collect the stormwater runoff generated on the site and store it in underground cellular attenuation tanks, these tanks allow runoff to infiltrate naturally through the soil beneath and into the ground water.

5.1 Design Parameters

The storm and foul network for the site is designed using hydraulic modelling software WinDes Micro Drainage. Refer to Figure 5.1 for the parameters assumed for the Storm Network. All attenuation designs are based on the infiltration rates and locations highlighted in section 5.3. The M5-60 value 18.4 below is based on the rainfall return period data specific to the site location and is taken from the interactive map on WinDes. The ratio R value is calculated using the following formula:

$$R = M5\ 60\ \text{min} / M5\ 2D$$

Figure 5-1: Storm Water Design Parameters

The storm drainage proposals incorporate the following elements;

- Sewers not surcharging in the 30-year event with 20% Climate Change
- Sewers not flooding in the 100-year event with 20% Climate Change.
- Class 1 Bypass Petrol Interceptors where runoff is collected from carriageway/parking areas.
- Sub-surface attenuation systems designed for storage of a 1 in 100-year storm plus 20% Climate Change.
- Interceptors (rain garden and tree pit) not taken into account in the 100 year event modelling.

The full Stormwater Design Report is attached in Appendix E. Surcharging can be seen occurring in the 30-year event. However, this is due to the attenuation systems working together and filling concurrently causing water to move upstream within the system. As can be seen by the flow/cap column of the pipe, the capacity of the pipes are greater than the predicted flow through them.

5.2 Suds Measures

The aim of these measures is to design the site drainage in a manner that mimics the natural drainage process for the site pre-development and reduce the impact of the development on the environment.

The SUDS measures selection process for this site were guided by the four pillars of SuDS which are Water Quantity, Water Quality, Biodiversity and Amenity. These prioritized the use of nature-based solutions with infiltration measures to promote groundwater discharge. This selection process took into account their practicability for use on the site and the constraints such as the topography and development layout so to create a SUDS Management Train.

The SUDS Management Train proposed for this site is evaluated from the point where rain falls, through the conveyance network through to how it is discharged within the site. The following SUDS measures have been integrated into the drainage design.

5.2.1 Bioretention Systems/Rain Gardens

Rain gardens are a form of Bioretention system which allows runoff to collect on its surface before infiltrating through vegetation and underlying soils. An overflow system integrated within the rain gardens will ensure that any exceedance above the capacity of these will be diverted to the stormwater system.

The planting type chosen for within the rain garden be chosen that it includes the following characteristics;

- Suits the surrounding landscape
- Native species
- High drought tolerance
- Inundation tolerance
- Pollutant tolerance




Figure 5-2 Raingarden with infiltration and overflow

All planting, backfilling and filter media will be in accordance with the recommendations of CIRIA C753.

5.2.2 Tree Pits

Tree pits have the ability to contribute to the storm water management strategy while also adding to the aesthetic value of the overall development. These can increase infiltration of the soil while also removing storm water through transpiration and interception.

Similar to the rain garden, it also provides an overflow to the piped collection system for exceedance events.

All planting, backfilling and filter media will be in accordance with the recommendations of CIRIA C753.




Figure 5-3 Tree Pit

5.2.3 Attenuation Storage Tanks

Cellular attenuation storage tanks have been chosen to maximise the allowable volume of water which can be stored on site, while also allowing infiltration to occur. The site will contain 6 separate tanks of varying volume which are hydraulically connected, allowing an extra safety measure in the event one isn't performing to its design capacity.




Figure 5-4 Attenuation Storage Tanks

Manholes immediately upstream and downstream of the tanks will have catch pits in order to prevent silt building up within the tanks.

During soakaway testing pits encountered rock at a depth of 1.2 and 1.6m therefore attenuation tank invert levels will be limited to these depths. Attenuation tank systems require a minimum of 0.3m cover under landscaped areas. This gives a maximum allowable depth of storage of between 0.9 and 1.3m. This restriction in tank height means a larger surface area is required for storage.

Sizing of tanks are based on the 1 in 100 year storm event + 20% climate change factor. As a further conservative approach, any interception and infiltration occurring as a result of the use of bioretention systems and tree pits is disregarded in this event.

Infiltration rates have been designed based on the soakaway test results given in Appendix G.

5.3 BRE 365 Infiltration Testing

Infiltration Testing was carried out on the 15th of June 2023 by MWP. The testing was carried out in 3 of the proposed soakaway locations (see locations in yellow below). The 3 trial pits were filled with water and levels were taken at intervals. The following soil infiltration rates (m/s) were calculated in accordance with section 3.2 of the BRE 365 document. The infiltration calculations are attached in Appendix G.

Soakaway 1 = 6.9×10^{-5} m/s

Soakaway 2 = 1.7×10^{-5} m/s

Soakaway 3 = 1.8×10^{-3} m/s

Infiltration testing was also carried out previously on this site on the 16th of December 2019 as part of a previous planning application. The soakaway tests were carried out on the western section of the site (see locations in red below). During the infiltration testing in December the site was noted as wet but subsoil conditions were dry. The winter infiltration rates are generally consistent with the summer results which indicates the site has suitable all year-round permeability. The following soil infiltration rates (m/s) were calculated in accordance with section 3.2 of the BRE 365 document. The infiltration calculations are attached in Appendix G.

Soakaway 4 = 3×10^{-4} m/s

Soakaway 5 = 5.5×10^{-5} m/s

Soakaway 6 = 7.5×10^{-5} m/s




Figure 5-5: Infiltration Testing

6. Public Lighting

The public lighting scheme within the development was designed using the Philips LumiStreet Gen2Micro LED fittings mounted on 6m high galvanised steel columns. The scheme is designed to be a Class P3 and the lighting design complies with Kerry County Council public lighting policy. The Proposed Public Lighting Layout drawing for the site is in Appendix H.

7. Telecom and other Electrical services

The site will be serviced with an underground telecom network with ducting to each block of apartments. This will facilitate the installation of fibre optic services for each of the dwellings.

Television Services:

Each apartment block will have its own television distribution network and will be cabled to provide each apartment with the option of free-to-air and satellite subscription services. This will be done via a centralised television distribution hub and this will eliminate the need for each apartment to have individual satellite dishes.

ESB Services:

It is proposed to incorporate an ESB MV substation into the Block B apartment building. Separate underground ESB supplies will be routed from here to the other apartment buildings. All ESB services within the site will be underground.

Electric Vehicle (EV) Charging:

Ducting will be provided throughout the site to all carparking spaces to facilitate the installation of EV chargers. Information in relation to the proposed EV charging units has been provided in Appendix I.

8. Road Geometry

The vertical alignment of the roads within the site have been designed in accordance with the “DMURS” by the Department of Transport, Tourism and Sport and the Department of Housing, Planning and Local Government (2019). The gradients of side roads are limited to a maximum of 2% within 7m of a junction. A Stage 1 DMURS Access Road Safety Audit Report 23824-6005 has been carried out. All recommendations have been considered and the site layout has been updated accordingly as per the designers feedback form attached in the RSA Report. A Traffic and Transport Assessment (TTA) has also been carried out as required as required for submission to KCC. The findings show the proposed residential development would be sustainable on the basis of the existing Cloonmore Avenue and Ballymullen Clash Link Relief Road Phase 1. The future provision of Phase 2 of the Link Relief Road would not be warranted to sustain the proposed residential development, on the basis of the foregoing Assessment. Please refer to report 23824-6004-TTA for the full Traffic and Transport Assessment details.

The internal road layout of the estate has been subjected to a swept path analysis of a bin lorry and a fire engine. These drawings are included in Appendix J. This analysis demonstrates how the internal site layout permits the movement of these vehicles around it given the low design speeds and residential nature of the site.

Appendix A

Confirmation of Feasibility

CONFIRMATION OF FEASIBILITY

Gearoid Fitzgerald

Reen Point
Blennerville
Tralee
Kerry
V92X2TK

29 May 2023

Uisce Éireann
Bosca OP 448
Oifig Sheachadta na
Cathrach Theas
Cathair Chorcaí

Irish Water
PO Box 448,
South City
Delivery Office,
Cork City.

www.water.ie

**Our Ref: CDS23003080 Pre-Connection Enquiry
Cloon Moore, ,, Tralee, Kerry**

Dear Applicant/Agent,

We have completed the review of the Pre-Connection Enquiry.

Irish Water has reviewed the pre-connection enquiry in relation to a Water & Wastewater connection for a Housing Development of 145 unit(s) at Cloon Moore, ,, Tralee, Kerry, (the **Development**).

Based upon the details provided we can advise the following regarding connecting to the networks;

- **Water Connection**
 - Feasible Subject to upgrades
 - In order to connect the proposed development an upgrade of the 100mm pipe to a 200mm is required up stream of the development (approximately 30m).
- **Wastewater Connection**
 - Feasible Subject to upgrades (Possibly)
 - No Stormwater will be accepted into the Wastewater Network, applicant to show at application stage how they intend to deal with Stormwater.
 - No Upgrades identified at present, DAP for Tralee Town will be available early 2024 which may identify upgrades to the network.

This letter does not constitute an offer, in whole or in part, to provide a connection to any Irish Water infrastructure. Before the Development can be connected to

our network(s) you must submit a connection application and be granted and sign a connection agreement with Irish Water.

As the network capacity changes constantly, this review is only valid at the time of its completion. As soon as planning permission has been granted for the Development, a completed connection application should be submitted. The connection application is available at www.water.ie/connections/get-connected/


Where can you find more information?

- **Section A** - What is important to know?
- **Section B** - Details of Irish Water's Network(s)

This letter is issued to provide information about the current feasibility of the proposed connection(s) to Irish Water's network(s). This is not a connection offer and capacity in Irish Water's network(s) may only be secured by entering into a connection agreement with Irish Water.

For any further information, visit www.water.ie/connections, email newconnections@water.ie or contact 1800 278 278.

Yours sincerely,

A handwritten signature in black ink, reading "Yvonne Harris", is written over a horizontal line.

Yvonne Harris
Head of Customer Operations

Section A - What is important to know?

What is important to know?	Why is this important?
Do you need a contract to connect?	<ul style="list-style-type: none"> • Yes, a contract is required to connect. This letter does not constitute a contract or an offer in whole or in part to provide a connection to Irish Water's network(s). • Before the Development can connect to Irish Water's network(s), you must submit a connection application <u>and be granted and sign</u> a connection agreement with Irish Water.
When should I submit a Connection Application?	<ul style="list-style-type: none"> • A connection application should only be submitted after planning permission has been granted.
Where can I find information on connection charges?	<ul style="list-style-type: none"> • Irish Water connection charges can be found at: https://www.water.ie/connections/information/charges/
Who will carry out the connection work?	<ul style="list-style-type: none"> • All works to Irish Water's network(s), including works in the public space, must be carried out by Irish Water*. <p>*Where a Developer has been granted specific permission and has been issued a connection offer for Self-Lay in the Public Road/Area, they may complete the relevant connection works</p>
Fire flow Requirements	<ul style="list-style-type: none"> • The Confirmation of Feasibility does not extend to fire flow requirements for the Development. Fire flow requirements are a matter for the Developer to determine. • What to do? - Contact the relevant Local Fire Authority
Plan for disposal of storm water	<ul style="list-style-type: none"> • The Confirmation of Feasibility does not extend to the management or disposal of storm water or ground waters. • What to do? - Contact the relevant Local Authority to discuss the management or disposal of proposed storm water or ground water discharges.
Where do I find details of Irish Water's network(s)?	<ul style="list-style-type: none"> • Requests for maps showing Irish Water's network(s) can be submitted to: datarequests@water.ie

<p>What are the design requirements for the connection(s)?</p>	<ul style="list-style-type: none"> • The design and construction of the Water & Wastewater pipes and related infrastructure to be installed in this Development shall comply with <i>the Irish Water Connections and Developer Services Standard Details and Codes of Practice</i>, available at www.water.ie/connections
<p>Trade Effluent Licensing</p>	<ul style="list-style-type: none"> • Any person discharging trade effluent** to a sewer, must have a Trade Effluent Licence issued pursuant to section 16 of the Local Government (Water Pollution) Act, 1977 (as amended). • More information and an application form for a Trade Effluent License can be found at the following link: https://www.water.ie/business/trade-effluent/about/ <p>**trade effluent is defined in the Local Government (Water Pollution) Act, 1977 (as amended)</p>


The map included below outlines the current Irish Water infrastructure adjacent the Development: To access Irish Water Maps email

Note: The information provided on the included maps as to the position of Irish Water's underground network(s) is provided as a general guide only. The information is based on the best available information provided by each Local Authority in Ireland to Irish Water.

Whilst every care has been taken in respect of the information on Irish Water's network(s), Irish Water assumes no responsibility for and gives no guarantees, undertakings or warranties concerning the accuracy, completeness or up to date nature of the information provided, nor does it accept any liability whatsoever arising from or out of any errors or omissions. This information should not be solely relied upon in the event of excavations or any other works being carried out in the vicinity of Irish Water's underground network(s). The onus is on the parties carrying out excavations or any other works to ensure the exact location of Irish Water's underground network(s) is identified prior to excavations or any other works being carried out. Service connection pipes are not generally shown but their presence should be anticipated.

Appendix B

Proposed Storm, Foul and Watermain Layout



FOUL STRUCTURE TABLE					FOUL NETWORK								
Name	Easting	Northing	Cover Level	Connected Pipes	Pipe Name	Size	Length	Slope	US IL	DS IL	MIN. COVER	MAX COVER	MATERIAL
FMH1	484557.081	614338.662	7.584	1.000 Inv. 6.050	1.000	225.000	42.125	1:200	6.050	5.839	1.422	1.578	UPVC
FMH2	484517.000	614325.701	7.529	1.001 Inv. 5.839 1.000 Inv. 5.839	1.001	225.000	45.471	1:200	5.839	5.612	1.578	1.668	UPVC
FMH3	484528.802	614281.789	7.393	1.002 Inv. 5.612 1.001 Inv. 5.612	1.002	225.000	18.243	1:184	5.612	5.513	1.668	1.897	UPVC
FMH4	484576.412	614278.465	7.753	2.000 Inv. 6.150	2.000	225.000	69.953	1:200	6.250	5.900	1.377	1.399	UPVC
FMH4 (1)	484528.981	614263.547	7.523	1.003 Inv. 5.513	3.001	225.000	23.341	1:199	5.900	5.783	1.378	1.380	UPVC
				1.002 Inv. 5.513	3.002	225.000	16.477	1:201	5.783	5.701	1.380	1.488	UPVC
				2.000 Inv. 5.899	3.003	225.000	12.428	1:200	5.701	5.639	1.488	1.666	UPVC
FMH5	484609.880	614222.544	7.762	3.004 Inv. 5.577	3.004	225.000	13.978	1:225	5.639	5.577	1.666	1.833	UPVC
FMH6	484543.542	614200.348	7.390	3.001 Inv. 5.900 3.000 Inv. 5.900	1.003	225.000	3.177	1:244	5.513	5.500	1.780	1.897	UPVC
FMH7	484537.258	614222.827	7.275	3.002 Inv. 5.783 3.001 Inv. 5.783									
FMH8	484529.840	614237.540	7.302	3.003 Inv. 5.701 3.002 Inv. 5.701									
FMH9	484527.197	614249.683	7.418	3.004 Inv. 5.639 3.003 Inv. 5.639									
FMH0_F (1)	484526.516	614261.544	7.392	1.003 Inv. 5.500									

STORM NETWORK							
Pipe Name	Size	Length	Slope	US IL	DS IL	MIN. COVER	MAX COVER
1.000	300.000	40.726	1:299	6.465	6.329	0.935	1.207
1.001	375.000	5.796	1:290	6.329	6.309	1.170	1.230
1.002	375.000	5.796	1:290	6.209	6.189	1.330	1.354
1.003	375.000	41.725	1:503	6.189	6.106	1.354	1.434
1.004	375.000	10.610	1:303	6.106	6.071	1.404	1.434
2.000	225.000	7.802	1:223	6.106	6.071	1.478	1.540
3.000	300.000	54.176	1:299	6.252	6.071	1.258	1.441
1.005	375.000	4.816	1:375	6.071	6.058	1.404	1.537
1.006	375.000	7.802	1:370	5.958	5.945	1.638	1.828
1.007	375.000	42.763	1:375	5.945	5.831	1.828	1.920
1.008	450.000	11.059	1:442	5.831	5.806	1.663	1.883
1.009	450.000	10.099	1:137	5.806	5.732	1.650	1.663
4.000	225.000	34.533	1:500	6.800	6.731	0.782	0.895
4.001	225.000	4.843	1:220	5.755	5.733	1.758	1.762
5.000	225.000	34.294	1:500	6.800	6.731	0.890	0.914
5.001	225.000	6.172	1:101	6.000	5.939	1.556	1.646
1.010	450.000	56.274	1:450	5.600	5.475	1.782	2.057
6.000	300.000	36.167	1:299	6.472	6.351	0.903	0.927
6.001	300.000	27.104	1:301	6.351	6.261	0.927	1.124
6.002	300.000	10.894	1:303	6.261	6.225	1.087	1.124
6.003	300.000	23.493	1:301	6.225	6.147	1.087	1.247
6.004	300.000	26.754	1:301	6.147	6.058	1.139	1.247
6.005	300.000	10.116	1:298	6.058	6.024	1.139	1.496
1.011	450.000	6.325	1:452	5.659	5.645	1.786	1.959
1.012	450.000	6.325	1:452	5.545	5.531	2.038	2.059
1.013	450.000	44.315	1:498	5.531	5.442	1.872	2.038
7.000	300.000	71.533	1:225	6.800	6.482	0.642	1.195
7.001	300.000	4.211	1:222	6.482	6.463	1.195	1.220
7.002	300.000	71.286	1:499	6.463	6.320	1.080	1.220

STORM STRUCTURE TABLE				
Structure Name	Eastings	Northings	Cover Level	Connected Pipes
SMH1	484523.493	614326.018	7.550	1.000 Inv. 6.465
SMH2	484562.113	614338.942	7.686	1.001 Inv. 6.329 1.000 Inv. 6.329
SMH3	484565.158	614334.011	7.726	1.002 Inv. 6.209 1.001 Inv. 6.309
SMH4	484568.204	614329.080	7.730	1.003 Inv. 6.189 1.002 Inv. 6.189
SMH5	484584.822	614290.808	7.728	1.004 Inv. 6.106 1.003 Inv. 6.106
SMH6	484596.506	614283.367	7.758	2.000 Inv. 6.106 3.000 Inv. 6.252
SMH7	484537.386	614264.762	7.670	1.005 Inv. 6.071 1.004 Inv. 6.071 2.000 Inv. 6.071 3.000 Inv. 6.071
SMH8	484589.048	614281.076	7.662	1.005 Inv. 6.071 1.004 Inv. 6.071 2.000 Inv. 6.071 3.000 Inv. 6.071
SMH9	484590.967	614276.658	7.783	1.006 Inv. 5.958 1.005 Inv. 5.958
SMH10	484592.885	614272.240	7.961	1.007 Inv. 5.945 1.006 Inv. 5.945
SMH11	484609.917	614233.015	7.939	1.008 Inv. 5.831 1.007 Inv. 5.831
SMH12	484614.322	614222.871	7.694	1.009 Inv. 5.806 1.008 Inv. 5.806
SMH13	484570.357	614213.534	7.807	4.000 Inv. 6.800
SMH14	484603.196	614224.215	7.625	4.001 Inv. 5.755 4.000 Inv. 6.731
SMH15	484574.138	614203.193	7.803	5.000 Inv. 6.800
SMH16	484606.753	614213.789	7.758	5.001 Inv. 6.000 5.000 Inv. 6.731
SMH17	484604.758	614219.630	7.607	1.010 Inv. 5.600 1.009 Inv. 5.732 4.001 Inv. 5.733 5.001 Inv. 5.939
SMH18	484520.813	614319.443	7.525	6.000 Inv. 6.472
SMH19	484531.018	614284.746	7.428	6.001 Inv. 6.351 6.000 Inv. 6.351
SMH20	484531.504	614257.646	7.535	6.002 Inv. 6.261 6.001 Inv. 6.261
SMH21	484529.816	614246.884	7.462	6.003 Inv. 6.225 6.002 Inv. 6.225
SMH22	484538.337	614224.991	7.544	6.004 Inv. 6.147 6.003 Inv. 6.147
SMH23	484541.833	614198.466	7.347	6.005 Inv. 6.058 6.004 Inv. 6.058
SMH24	484551.461	614201.570	7.670	1.011 Inv. 5.659 1.010 Inv. 5.475 6.005 Inv. 6.024
SMH25	484550.288	614207.786	7.829	1.012 Inv. 5.545 1.011 Inv. 5.645
SMH26	484549.115	614214.002	7.794	1.013 Inv. 5.531 1.012 Inv. 5.531
SMH27	484535.456	614256.159	7.587	1.013 Inv. 5.442
SMH28	484557.187	614166.615	7.824	7.000 Inv. 6.800
SMH29	484625.167	614188.880	7.827	7.001 Inv. 6.482 7.000 Inv. 6.482
SMH30	484626.702	614184.959	7.833	7.002 Inv. 6.463 7.001 Inv. 6.463
SMH0_F (2)	484558.750	614163.416	7.550	7.002 Inv. 6.320

NOTES

GENERAL NOTES

1. ALL DRAWINGS ARE TO BE READ IN CONJUNCTION WITH ALL RELEVANT SPECIFICATIONS, BILLS OF QUANTITIES, ARCHITECTURAL, SERVICES AND ENGINEERING DRAWINGS.

2. ANY DISCREPANCIES BETWEEN THESE DOCUMENTS SHALL BE BROUGHT TO THE ATTENTION OF THE ENGINEER

3. ALL DIMENSIONS ARE IN MM UNLESS NOTED OTHERWISE

4. ALL LEVELS ARE IN METRES RELATED TO ORDNANCE DATUM.

5. DRAWINGS ARE NOT TO BE SCALED

LEGEND

SITE BOUNDARY

SITE OWNERSHIP BOUNDARY

PROPOSED FOUL DRAIN

PROPOSED FOUL MANHOLE

PROPOSED STORM DRAIN

PROPOSED STORM MANHOLE

EXISTING COMBINED DRAIN

PROPOSED ATTENUATION TANK

PROPOSED PETROL INTERCEPTOR

WAYLEAVE

PROPOSED GULLY


PROPOSED BIORETENTION RAIN GARDEN

NOTE

ALL ATTENUATION SYSTEMS ARE CONNECTED TO ENHANCE INFILTRATION POTENTIAL TO ALL ELEVATIONS AND RETURN PERIOD

NOTE

FOR BIORETENTION RAIN GARDEN DETAILS REFER TO DRAWING 23824-MWP-00-00-DR-C-2105



D01 10.08.23
REV/ DATE

ISSUED FOR INFORMATION
DESCRIPTION

R.H
BY

I.B
APP

MWP

ENGINEERING AND ENVIRONMENTAL CONSULTANTS

CORK | TRALEE | LONDON | LIMERICK

mwp.ie

PROJECT:
CLOONMORE REGENERATION LRD,
TRALEE, Co.KERRY

CLIENT:
TULFARRIS CG LTD

TITLE:
PROPOSED COMBINED DRAINAGE LAYOUT

DRAWN:
RH

CHECKED:
GF

APPROVED:
IB

PROJECT NUMBER:
23824

DATE:
10/08/2023


SCALE @ A1:
1:500

STATUS DESCRIPTION
FOR INFORMATION

STATUS:
S2

DRAWING NUMBER:
23824 - MWP - 00 - 00 - DR - C - 2100

REV:
P01



- NOTES:
1. ALL DRAWINGS ARE TO BE READ IN CONJUNCTION WITH ALL RELEVANT SPECIFICATIONS, BILLS OF QUANTITIES, ARCHITECTURAL SERVICES AND ENGINEERING DRAWINGS.
 2. ANY DISCREPANCIES BETWEEN THESE DOCUMENTS SHALL BE BROUGHT TO THE ATTENTION OF THE ENGINEER.
 3. ALL DIMENSIONS ARE IN MILLIMETRES, UNLESS NOTED OTHERWISE.
 4. ALL LEVELS ARE IN METRES RELATED TO ORDINANCE DATUM.
 5. DRAWINGS ARE NOT TO BE SCALED.

WATERMAIN LEGEND:	
	EXISTING WATERMAIN
	NEW 150mm DIA WATERMAIN PIPE (UNO)
	NEW 110mm DIA WATERMAIN PIPE (UNO)
	IRISH WATER APPROVED FIRE HYDRANT
	IRISH WATER APPROVED WASHOUT HYDRANT
	IRISH WATER APPROVED SLUICE VALVE
	IRISH WATER APPROVED AIR VALVE
	IRISH WATER APPROVED METER

PD1	25-08-23	ISSUE FOR PLANNING	O.B.	I.B.
REV	DATE	DESCRIPTION	BY	APP
PROJECT: CLOONMOORE REGENERATION LRD, TRALEE, Co. KERRY.				
TITLE: WATERMAIN LAYOUT				
CLIENT: TULFARRIS CG LTD				
DRAWN: O.B.	CHECKED: G.F.	APPROVED: I.B.		
PROJECT NUMBER: 23824	DATE: 25/08/2023	SCALE @ A1: 1:500		
STATUS DESCRIPTION: FOR INFORMATION			STATUS: S2	
DRAWING NUMBER: 23824 - MWP - 00 - 00 - DR - C - 2104			REV: P01	

PROPOSED WATERMAIN LAYOUT
SCALE: 1:500

Appendix C

Water Mains and Foul Calculations for the site

Irish Water Preconnection Application Form Calculations

Site Details

Address

Cloonmore

Co. Kerry

Calculations based on current phase only.

Watermains

Occupancy Levels

	No.	Occupancy	Total	
Number of Houses	145	2.7	391.5	Persons
			392	Persons

2.7 Assumed Occupancy Level

Source: Irish Water Code of Practice for Water

Average Usage	58800	l/day
	0.681	l/s
Average Day/ Peak Week Demand	0.851	l/s
Peak Demand	4.253	l/s

Average Daily usage 150 l/person/day

1.25 times average daily domestic demand

5 times average day/peak week demand

Source: Irish Water Code of Practice for Water

Wastewater

Hydraulic Load

Dry Weather Flow	64670	l/day
	0.748	l/s
Design Foul Flow	4.491	l/s

Dry Weather Flow 446 l/dwelling/day

Source: Irish Water Code of Practice for Wastewater

Domestic Wastewater peak factor 6

Source: Irish Water Code of Practice for Wastewater

Surface Water Allowance

Gross Site Area	1.55	ha
Catchment Area	0.023	ha
Intensity	8	mm/hr
Volumetric Runoff Coefficient Cv	0.9	-
	1.300	-
Flow	0.605	l/s

Buildings, Hardstanding and grass. Area from Architect

1.5% of Gross Site Area

Slopes less than 2% present and 100% AEP event

Design Flow	5.096	l/s
-------------	-------	-----

Appendix D

Maintenance Plan and Schedule for Storm Drainage Infrastructure



Maintenance Plan and Schedule for Storm Drainage Infrastructure

Cloonmore Regeneration LRD, Tralee, Co. Kerry

On behalf of Tulfarris CG Ltd.

August 2023

Contents

1. Introduction 1

1.1 Location and Proposed Development 1

2. Recommended Maintenance..... 2

2.1 Storm Drains 2

2.2 Kingspan Klargester Bypass Separators 2

2.3 Operation & Maintenance requirements for attenuation storage tanks as per CIRIA C753 – SuDS Manual 2015 & Wavin Aquacell O&M Manual 2

2.4 Operation & Maintenance requirements for silt traps as per CIRIA C753 – SuDS Manual 2015 3

2.5 Operation & Maintenance requirements for hydro brakes as per CIRIA C753 – SuDS Manual 2015 ... 3

2.6 External drainage system – Drainage adjacent to road..... 3

Figures

Figure 1-1: Aerial Image of Proposed Site 1

Appendices

- Appendix A - Proposed Maintenance and Inspection Schedule Record Sheet
- Appendix B - Product Data Sheets

Project No.	Doc. No.	Rev.	Date	Prepared By	Checked By	Approved By	Status
23824	6010	A	10/08/2022	G Fitzgerald A O Donnell	IB	IB	Final

MWP, Engineering and Environmental Consultants
Address: Park House, Bessboro Road, Blackrock, Cork, T12 X251
www.mwp.ie



1. Introduction

MWP were commissioned by Tulfarris CG Ltd. to provide a design for the civil utilities serving the site namely, stormwater, foul water, public lighting, and water supply in connection with a planning application for proposed Residential Development at Cloonmore, Tralee, Co. Kerry. The document outlines the design intent for the plan and schedule for the future maintenance of the site drainage infrastructure to mitigate against the risk of flooding on the public road and the site in the interest of amenity and traffic safety.

1.1 Location and Proposed Development

The site is located to the south of Austin Stack's Park and within the townland of Boherbee to the east of Tralee Town Center. University Hospital Kerry is located to the southwest of the site. See Figure 1-1 below for an aerial image of the site. The site is relatively flat, levels on the site vary 8.116mOD on the east to 7.020mOD (AOD Above Ordnance Datum) on the west with the site generally falling from east to west. The proposed development is currently predominantly a greenfield site. The site area is approximately 1.55ha. The site is located to the east of Tralee town centre. The figure below shows the proposed site within the land parcel. MWP were appointed to prepare a maintenance plan and schedule with respect to this development.



Figure 1-1: Aerial Image of Proposed Site

2. Recommended Maintenance

All elements of the drainage system should be inspected following a major storm event. Maintenance should be carried out in tandem with the specification outlined by the manufacturer and be conducted to whichever is the most onerous. When carrying out maintenance, it is essential that a record of inspection and maintenance on all elements is kept and updated when required. A proposed template to record the maintenance and inspections conducted on the site can be found in Appendix A. Product sheets for the critical elements for the storm sewer are provided in Appendix B.

2.1 Storm Drains

It is recommended all storm drains are cleaned every 6 months. Further recommendation is shown below:

Maintenance Schedule	Required Action	Typical Frequency
Routine Maintenance	Inspection	Monthly
	Litter/debris removal	Monthly or as required
Occasional Maintenance	Sediment removal – silt build-up should be removed	Every 6 months
Remedial Maintenance	Repair (as a result of damage or vandalism)	As required

2.2 Kingspan Klargestor Bypass Separators

Kingspan Klargestor recommends checking the oil levels after the first 3 months. This will give an indication on when the separators should be maintained.

2.3 Operation & Maintenance requirements for attenuation storage tanks as per CIRIA C753 – SuDS Manual 2015 & Wavin Aquacell O&M Manual

Maintenance Schedule	Required Action	Typical Frequency
Regular Maintenance	Inspect and identify areas that are not operating correctly. Take action where required	Monthly for 3 months. Yearly thereafter.
	Remove debris from catchment surface. (where it may cause risk to performance.)	Monthly
	For systems where rainfall infiltrates into the tank from above, check surface of filter for blockage by sediment, algae or other matter; remove and replace surface infiltration medium as necessary.	Annually
	Remove sediment from pre-treatment structures, isolation rows, and/ or internal forebays	Annually, or as required
Remedial Maintenance	Repair/rehabilitate inlets, outlet, overflows and vents	As required.

Monitoring	Inspect/check all inlets, outlets, vents and overflows to ensure that they are in good condition and operating as designed	Annually & following large storms
	Survey inside of system for sediment build-up and remove if necessary	Every 6 months or as required.

2.4 Operation & Maintenance requirements for silt traps as per CIRIA C753 – SuDS Manual 2015

Maintenance Schedule	Required Action	Typical Frequency
Routine Maintenance	Inspection	Monthly
	Litter/debris removal	Monthly or as required
Occasional Maintenance	Sediment removal – silt stores should be emptied	Every 6 months
Remedial Maintenance	Repair (as a result of damage or vandalism)	As required

2.5 Operation & Maintenance requirements for hydro brakes as per CIRIA C753 – SuDS Manual 2015

Maintenance should be carrying out in tandem with the specification outlined by the manufacturer. As a general guide, the following requirements should be met:

Maintenance Schedule	Required Action	Typical Frequency
Routine Maintenance	Inspection	Monthly
	Litter/debris removal	Monthly or as required
Occasional Maintenance	Sediment removal – silt stores should be emptied	Every 6 months
Remedial Maintenance	Repair (as a result of damage or vandalism)	As required

2.6 External drainage system – Drainage adjacent to road

The drainage system should be inspected regularly to coincide with the aforementioned specification. A general guideline is shown below:

Maintenance Schedule	Required Action	Typical Frequency
Routine Maintenance	Inspection	Monthly
	Litter/debris removal	Monthly or as required
Occasional Maintenance	Sediment removal – silt stores should be emptied	Every 6 months
Remedial Maintenance	Repair (as a result of damage or vandalism)	As required

Appendix A

Proposed Maintenance and Inspection Schedule Record Sheet

[illegible]

Appendix B

Product Data Sheets

015319
NSBE010-NSBE125 Class 1 Bypass Separator
Installation & Maintenance Guidelines



Kingspan Environmental Service Contact Numbers:

GB: 0844 846 0500

NI: 028 3025 4077

IRL: 048 3025 4077

Enclosed Documents

DS1155	NSBE010-NSBE030 Class 1 Bypass Separators
DS1254	NSBE036 Class 1 Bypass Separator
DS1224	NSBE040 & NSBE050 Class 1 Bypass Separators
DS1225	NSBE075-NSBE125 Class 1 Bypass Separators

Issue	Description	Date
04	CC1180 Introduction of NSBE036	May 2014

HEALTH & SAFETY

These warnings are provided in the interest of safety. You must read them carefully before installing or using the equipment.

It is important that this document is retained with the equipment for future reference. Should the equipment be transferred to a new owner, always ensure that all relevant documents are supplied in order that the new owner can be acquainted with the functioning of the equipment and the relevant warnings.

Installation should only be carried out by a suitably experienced contractor, following these guidelines.

We recommend the use of a dust mask and gloves when cutting GRP components.

Electrical work should be carried out by a qualified electrician.

Contaminated surface water can contain substances harmful to human health. Any person carrying out maintenance on the equipment should wear suitable protective clothing, including gloves. Good hygiene practice should also be observed.

Access covers should be selected with reference to the location of the unit and traffic loads to be accommodated. These are not (normally) part of the Separator supply.

When covers are removed precautions must be taken against personnel falling into the unit.

Should you wish to inspect the operation of the equipment, please observe all necessary precautions, including those listed below, which apply to maintenance procedures.

Ensure that you are familiar with the safe working areas and accesses. Ensure that the working area is adequately lit.

Take care to maintain correct posture, particularly when lifting. Use appropriate lifting equipment when necessary. Keep proper footing and balance at all times. Avoid any sharp edges.

OIL ALARM SYSTEMS

PPG3 requires that the oil level alarm be fitted, tested and commissioned by a competent Installer. This is to ensure that the excessive oil probe is calibrated correctly, raising an alarm when 90% of the recommended maximum oil storage volume is reached. Should the oil level alarm fail to provide an early warning, excessive oil could pass through the separator, thus polluting the environment. This could result in substantial cleanup costs and legal action being taken under the water resources act 1991.

MAINTENANCE

The correct ongoing maintenance is essential for the proper operation of the equipment. Operators who rely on oil level alarms to prompt them to service separators between maintenance intervals run the risk of polluting should the alarms not work, hence the ongoing functional assessment of the oil alarm systems is fundamental if pollution incidents are to be avoided.

The removal of sediment and retained oil/grease should be carried out by a contractor holding the relevant permits to transport and dispose of such waste. The contractor must refer to the guidelines in this document.

CONTENTS

	Page
HEALTH & SAFETY	2
1 Introduction.....	5
1.2 Handling & Storage	5
1.3 Site Planning	5
2 Installation	6
2.1 Installation – General.....	6
2.2 Separator Installation.....	7
2.3 Pipework Connections.....	7
2.4 Oil Level Alarm Neck Fitting	8
2.5 Alarm Installation	8
3 Operation.....	9
4 Maintenance.....	10
4.1 Waste Removal and Servicing	10
4.2 Waste Removal Procedure – Oil & Silt.....	10
4.3 Checking the Coalescer Assembly.....	10
4.4 Removing the coalescer assembly.....	11
4.5 Cleaning the coalescer assembly/ Media Replacement.	11
4.6 Replacing the coalescer assembly.....	11
5 Emergencies	12

Appendices

Separator Maintenance Log

CE	
<p>Kingspan Environmental College Road North Aston Clinton Aylesbury Buckinghamshire HP22 5EW United Kingdom</p>	
13	
En 858 : Separator systems for light liquids	
GRP Glass Reinforced Plastic Tank	
Bypass Separators NSB003 - NSB150	
Class 1	
Watertightness	Passed
Structural Testing	Passed
Hydraulic Efficiency	Passed

1 Introduction

- 1.1.1 These Guidelines represent Best Practice for the installation of the above Separator Units. Many years of specialist experience has led to the successful installation of thousands of separator units. It must be noted, however, that these Guidelines are necessarily of a general nature. It is the responsibility of others to verify that they are appropriate for the specific ground conditions and in-service loads of each installation. Similarly, any information or advice given by our employees or agents regarding the design of an installation must be verified by a qualified specialist (e.g. Civil engineering consultant).
- 1.1.2 For guidance of Separator selection and application, please refer to the most recent issue of Environment Agency Guidelines pollution prevention guidelines No. 3 (PPG3).and BS En 858

1.2 Handling & Storage

- 1.2.1 Care must be taken to ensure that units are not damaged during delivery and handling on site. Please take care and place unit so that it cannot fall and become damaged
- 1.2.2 The design requirements of these products will frequently mean that the centre of gravity of the unit is "offset". Care must therefore be taken to ensure that the unit is stable when lifting. Rainwater may also collect inside units, particularly if they have been stored on site prior to installation, adding weight and increasing instability. Check units before lifting and pump out any excess water.
- 1.2.3 When lifting units, use webbing slings of a suitable specification. Do not use chains.
- 1.2.4 A suitable spreader bar should be used to ensure that units are stable and that loads are evenly distributed during lifting. When lifting separators, a spreader bar should be used where the slings would otherwise be at an angle > 30 degrees to the vertical.
- 1.2.5 Lifting equipment should be selected by taking into account the unit weight, length and the distance of lift required on site.
- 1.2.6 We accept no responsibility for the selection of lifting equipment.
- 1.2.7 Whenever units are stored or moved on site, ensure that the storage location is free of rock, debris and any sharp objects, which may damage the unit. The units must be placed on ground, which is flat, and level and the unit orientated onto its side with even support. Do not roll separators.

1.3 Site Planning

The following points should be considered before installation of the equipment:

- 1.3.1 The discharge must have the consent of the relevant Environmental Regulator.
- 1.3.2 The installation should have Planning and Building Control approval.
- 1.3.3 Consider installing flow cut-off valves to isolate the separator in an emergency or during site cleaning operations. See Environment Agency Guidelines PPG3.
- 1.3.4 We will fit a tube to receive the alarm probe. This tube provides protection and ensures that the probe is positioned at the correct level to sense the oil build up. The tube design and probe level setting assumes the use of our standard oil alarm system and may not be suitable for other alarm supplier's equipment. The probe tube may be fitted either within the neck or within the body of the unit. It should be extended to ground level when fitted in the body of the tank and you should make provision to extend the tube to the required height before backfilling. Consult the alarm supplier's instructions for their detailed fitting installation instructions.
- 1.3.5 Consider venting of the unit. Comply with local regulations. In the UK, comply with the following regulations. For Petrol Stations: Health and Safety Guidance Note 41 (HS(G)41). For other applications: BS8301: 1985 (obsolescent) BS EN 752 Building Drainage. Adequate ventilation should be provided to the separator. The ventilation pipe should be as short as is practicable and be terminated not less than 2.5m above paving nor less than 1m above the head of an openable window or other opening into a building within a horizontal distance of 3m. Each neck should be vented independently, we advise against joining these below ground prior to their rising as vent stacks.
- 1.3.6 Consider installation of a sampling point downstream of the separator. There is no suitable facility to effectively sample the wastewater from inside the unit.

- 1.3.7 Uncontaminated run off such as roof water should be excluded from separators. (EA Guidelines PPG3.)
- 1.3.8 Ground conditions and water table level should be assessed. If the water table will be above the base of the units at any time of the year, adequate concrete backfill must be provided to avoid flotation. In poorly draining ground, consideration should also be given to the likelihood of flotation due to surface water collecting in the backfill, and an appropriate installation method devised to avoid this.
- 1.3.9 If the discharge is to a soakaway, a porosity test should be carried out as part of the assessment of suitability for sub-soil drainage.
- 1.3.10 The separator must be installed at a level, which will allow connection to the incoming drain and a free discharge at the system outlet. The water table must be below the discharge outlet.
- 1.3.11 Do not install the unit deeper than necessary, ensure that you purchase extension shaft kits. The minimum invert depth of the unit is shown on the customer drawing.
- 1.3.12 Adequate access must be provided for routine maintenance. Vehicles should not be permitted within a distance equal to the depth of the unit, unless suitable structural protection is provided to the installation.
- 1.3.13 There must be at least 1 metre of clear, level ground all around the access covers to allow for routine maintenance.
- 1.3.14 It is essential that a mains water supply is accessible for routine cleansing and refilling after removal of waste material and liquid.
- 1.3.15 Provide electrical supply for alarm system.
- 1.3.16 Installation should only be carried out by suitably qualified and experienced contractors in accordance with current Health and Safety Regulations. Electrical work should be carried out by a qualified electrician, working to the latest edition of IEE wiring regulations.
- 1.3.17 This unit is designed to operate with gravity in and out flows. The unit is not designed to operate with a pumped influent.

2 Installation

2.1 Installation – General

- 2.1.1 When units are installed in unstable ground conditions where movement of the surrounding material and/or unit may occur, the connecting pipework should be designed to minimise the risk of damage from differential movement of the unit(s) and/or surrounding material.
- 2.1.2 For separators with burial depths greater than 1000mm from cover level to the top of the unit, specific site conditions should be taken into consideration and the backfill designed to bear any loads which may be applied during and after installation to prevent the tank being subjected to these loads.
- 2.1.3 The excavation must be deep enough to provide bedding and cover depth as determined by the type of surface pavement and loading. Asphalt and concrete pads should extend a minimum of 300mm horizontally beyond the unit in all directions.
- 2.1.4 In situations where the excavation will not maintain a vertical wall, it will be necessary to shore up the sidewalls of the excavation with suitable trench sheets and bracing systems to maintain a vertical wall from the bottom to the top of the excavation. DO NOT completely remove the shoring system until the backfilling is complete, but before the concrete fully hardens.
- 2.1.5 In areas where the water table is above the bottom of the excavation and/or the excavation is liable to flood, the excavation should be dewatered using suitable pumping equipment and this should continue until the installation is complete.
- 2.1.6 During installation care must be taken to ensure that the body of the unit is uniformly supported so that point loads through the unit are avoided.
- 2.1.7 The concrete Specification is not a site specific installation design.

GENERAL CONCRETE SPECIFICATION IN ACCORDANCE WITH BS EN 206-1 (BS 8500-1)		
TYPE OF MIX		(DC) DESIGN
PERMITTED TYPE OF CEMENT		BS 12 (OPC): BS 12 (RHPC): BS 4027 (SRPC)
PERMITTED TYPE OF AGGREGATE (coarse & fine)		BS 882
NOMINAL MAXIMUM SIZE OF AGGREGATE		20 mm
GRADES: C25 /30 C25 /30 C16 /20		REINFORCED & ABOVE GROUND WITH HOLDING DOWN BOLTS REINFORCED (EG. FOR HIGH WATER TABLE) UNREINFORCED (NORMAL CONDITIONS)
MINIMUM CEMENT CONTENT	C30 C20	270 - 280 Kg/M ³ 220 - 230 Kg/M ³
SLUMP CLASS		S1 (25mm)
RATE OF SAMPLING		READY MIX CONCRETE SHOULD BE SUPPLIED COMPLETE WITH APPROPRIATE DELIVERY TICKET IN ACCORDANCE WITH BS EN 12350-1
NOTE: STANDARD MIXES SHOULD NOT BE USED WHERE SULPHATES OR OTHER AGGRESSIVE CHEMICALS EXIST IN GROUND WATER		

2.2 Separator Installation

- 2.2.1 Excavate a hole of sufficient length and width to accommodate the tank and a minimum 225mm concrete surround and to a depth, which allows for the burial depth of the unit plus concrete base slab and haunch.
- 2.2.2 Construct a suitable concrete base slab appropriate to site conditions. Ensure that the slab is flat and level.
- 2.2.3 When the concrete base slab has set enough to support the installed load, add a concrete haunch so as to provide even support under the unit and then lower the unit onto the haunch using suitable webbing slings and lifting equipment.
- 2.2.4 **Pour no more than 300-mm depth of clean water into the unit, avoiding shock loads. For units with more than one chamber, add water to each chamber simultaneously. DO NOT OVERFILL; the unit is not designed to hold water whilst unsupported.**
- 2.2.5 **Place concrete backfill to approximately 300mm depth under and to the sides of the tank ensuring good compaction to remove voids. DO NOT use vibrating pokers. Continue adding concrete backfill, simultaneously keeping the internal water level no more than 200 mm above the backfill level at all times, until the backfill is just below the underside of the outlet drain, giving sufficient room to connect the inlet and outlet pipework.**
- 2.2.6 Connect inlet and outlet drains and vent pipes when safe access to the backfill can be gained.

2.3 Pipework Connections

- 2.3.1 In all cases, ensure that the outlet pipework level is maintained for correct operation. (Unless specified on the order, the fall across the unit will be as per the customer drawings).
- 2.3.2 Small units are generally fitted with **PVCu spigots** to both the outlet and the inlet.
- 2.3.3 Connect using the same size PVCu socket or a suitable reducer.
- 2.3.4 Larger units are generally fitted with **Our GRP** manufactured sockets.
- 2.3.5 The connecting pipework should be pushed into the socket. Ensure that the seal is secure and watertight before backfilling the pipe.

- 2.3.6 Alternatively, proprietary **flex seal couplings** can be obtained to fit over the outside of the site pipework and the outside of the GRP socket. When using this connection method, please be aware that the outside GRP laminate is not perfectly regular and that you may need to use a sealant on the outside diameter of the GRP. Take care not to over tighten the coupling when connecting to the GRP and ensure that the seal is secure before backfilling the pipe. Drawing 403144 provides the ID of our Bypass GRP sockets. The OD is variable, as the wall thickness can be up to 15-20 mm. If purchasing a flexseal coupling for use with clay /concrete, we suggest that a size 110 mm larger than the ID is selected.

2.4 Oil Level Alarm Neck Fitting

- 2.4.1 We will fit a tube to receive the oil alarm probe. This provides protection and ensures that the probe is positioned at the correct level to sense oil build up.
- 2.4.2 See alarm supplier information and ensure that the probe is placed within the tube and can be accessed from ground level.
- 2.4.3 Continue backfilling with concrete over the tank body to the required level. Build up a shell of concrete, minimum 225mm thick, around the access shaft(s). Temporarily strut the access shaft to avoid distortion.
- 2.4.4 Where we supply an extension shaft to meet a deeper invert requirement, a coalescer extension tube will be required. When fitting, ensure that the tube is extended to just below the surface so that the coalescer can easily be removed. Remove the coalescer from the unit before adding the extension tube. When refitting, ensure that the coalescer is correctly inserted and fully pushed into the base fitting. This is important and you must ensure that the coalescer is correctly located before putting the unit in to operation. Reattach the bracket to the extended neck so it lines up with the hole in the coalescer.
- 2.4.5 It is advisable to seal the joints on the extension shafts (particularly on sites with high ground water) with proprietary sealant or by GRP lamination. Temporarily strut the extension neck(s) to avoid distortion during back filling. Where more than one neck section is required to suit a deep invert, consider back-filling section by section. If the extension neck is too long, it can be trimmed using a fine-toothed saw. The original fixing hole bolting the coalescer to the neck should be sealed.
- 2.4.6 Ensure that the vent socket if cut out, is replaced elsewhere. The maximum recommended inlet invert is 2000mm (using 500mm long extension sections). If you are installing a unit deeper than this then you must make your own arrangements for removing and replacing the coalescer. Consideration must be given to the depth of lift involved.
- 2.4.7 Continue back-filling, ensuring minimum 225mm concrete thickness around the access shaft/ extension neck and alarm access tube (as applicable).
- 2.4.8 Mains powered Alarm Systems. See alarm suppliers installation instructions. Lay 82mm diameter PVCu underground ducting between the alarm panel location and the alarm probe position. The ducting should be 500mm below ground level and fitted with a drawstring for later cable insertion. Any changes of direction should be by long radius bend. If necessary, drill a suitable hole in the access shaft adjacent to the alarm probe terminal box, to accept the ducting and seal.
- 2.4.9 In traffic areas a suitable top slab must be constructed. The top slab should bear on a suitable foundation to prevent superimposed loads being transmitted to the unit and access shafts. Loads applied to covers and frames must bear on the top slab, not the access shaft.
- 2.4.10 The unit should be filled with clean water up to the invert level of the outlet pipe. Ensure the unit identification is placed/ marked inside the neck for future information. The unit is now ready for use.

2.5 Alarm Installation

- 2.5.1 Install the alarm probe and control panel, as per the Suppliers Alarm Installation Guidelines. Ensure that the probe is positioned correctly for the required storage of oil. The table below indicates the maximum volume of oil to be stored and the depth of floating oil expected in the separation chamber.

Unit	Required Minimum Oil Storage volumes in litres	Max. (100%)Depth of floating oil (Static)
NSBE010	150 litres	320mm
NSBE015	225 litres	335mm
NSBE020	300 litres	335mm
NSBE025	375 litres	385mm
NSBE030	450 litres	385mm
NSBE036	540 litres	250mm
NSBE040	600 litres	420mm
NSBE050	750 litres	430mm
NSBE075	1125 litres	430mm
NSBE100	1500 litres	435mm
NSBE125	1875 litres	435mm

3 Operation

- 3.1.1 The unit is sized on treating a defined area and rainfall (5 mm/hour) EN.858 Part 1 and using the factor provided in the Environment agency guidelines PPG3. (0.0018 = 6.5mm/hr) The unit will treat the entire flow i.e. NSBE015 will treat a flow of 15 litres per second. If the flow is greater than this then the excess flow will bypass the main treatment chamber. A NSBE015 unit will work in bypass mode over 15 and up to 150 litres per second. Flows in excess of this will back up on to the site. During a storm, the rain falls and flushes any surface debris, silt or oil into the tank. This first flush, up to the maximum rated flow is fully treated. As the severity of the storm increases, so does the rate of flow increase. The liquid entering the separator after the first flush tends to be cleaner and so, in lower risk applications, is allowed to bypass the oil separation chamber for directly discharge.
- 3.1.2 The bypass unit has three chambers. The entire flow up to the units listed flow rating is fully treated and passes through all chambers. (E.g. NSBE015 treats 15 litres per second.)
- 3.1.3 Flows in excess of this rating will bypass the separation chamber and the liquid passes untreated to the outlet chamber.
- 3.1.4 The first chamber will accumulate silt and grit. The maximum volume that can be retained is the rating x 100 e.g. a NSBE015 is capable of holding 1500 litres of silt.
- 3.1.5 The second / separating chamber is sized to separate oil at the rated flow rate and to accumulate the required oil storage volume. A NSBE015 maximum oil storage volume is 225 litres. An oil probe should be positioned to detect the accumulation of oil when there is no or low flow conditions. The probe should be positioned so that the alarm operates at 90% of the rated oil storage volume.
- 3.1.6 In bypass flow conditions, the flow moves directly from the inlet to the outlet chamber avoiding the separating chamber.
- 3.1.7 Separators are purchased as Class 1 units. Class 1 Bypass Separators are fitted with a removable coalescer which also includes media to further improve the discharge quality. The coalescer media requires maintenance.
- 3.1.8 Bypass Class 1 Separators are not effective for the removal of soluble or emulsified pollutants such as oil/detergent mixes found in vehicle wash effluents. With permission such discharges should be drained to the foul sewer. Consult our technical department for Separation equipment to meet these applications.

4 Maintenance

4.1 Waste Removal and Servicing

- 4.1.1 Separated light liquid **must** be removed from separator when the oil capacity has been reached.
- 4.1.2 An oil level alarm system is available for purchase which gives warning when the separated light liquid/water interface level reaches 90% of the maximum recommended oil storage volume.
- 4.1.3 Separators should be inspected at least every six months or more frequently if experience dictates. A log should be maintained detailing the depth of oil found, any oil volume removed and any silt removal or cleaning carried out. A specimen maintenance log is included in the appendices.
- 4.1.4 Every site is different, in respect to the amount and type of silt generated by the drain design and installation. Frequently, the construction programme itself generates large and perhaps unusual quantities of silt and grit. We do recommend that following the initial installation, an inspection of the separator contents be made to check that building rubble has not entered the unit. Further inspections at 3 and 6 months should be made so as to be able to assess the volumes of silt and oil accumulated. The inspection and emptying programme can then be defined following the first 6 months site experience. We recommend leaving a maximum interval between inspections of 6 months.
- 4.1.5 Alarm probes should be removed and cleaned with water whenever waste material is removed from the separator. Please note the alarm may alert until the liquid level is replaced.
- 4.1.6 **Separator waste is a “special waste” under the terms of The Waste Management Code of Practice. The Code imposes a duty of care on the waste producer to ensure that the Cleansing contractor is registered with the Environment Agency and that the final disposal of the waste is to a licensed facility.**
- 4.1.7 You should consider the purchase of a maintenance service, which includes bi-annual inspections, removal of oil and silt, cleaning of the alarm probe and cleaning or replacement of the coalescer (where appropriate).

4.2 Waste Removal Procedure – Oil & Silt

- 4.2.1 **Oil can only be effectively removed when there is no flow entering the unit. Isolate the unit and prevent flow from entering. Always remove the oil before attempting to remove the coalescer. If this is not done, when the coalescer is withdrawn the oil can coat the media surface and when replaced the oil may be forced through the media, contaminating the effluent.**
- 4.2.2 Remove the access cover and lower the desludging hose in to the separation chamber. Draw off the surface oil.
- 4.2.3 If removing the silt, lower the desludge hose to the base of the tank and empty the contents of the chamber. Ensure that you access and clean both the inlet and the separation compartments.
- 4.2.4 Remove the alarm probe, if fitted, clean with water and replace.
- 4.2.5 Consider the period of time that the coalescer has been installed and consider removing and inspecting (cleaning or replacing) the coalescer media. If removed, ensure that it is correctly replaced and secured into position. Replace the access covers. It is best to lower the water level to aid re-fitting.
- 4.2.6 Re-fill the separator with clean water up to the outlet level.
- 4.2.7 If an alarm is fitted, it will display an alarm condition until the separator is re-filled. Check alarm operation when unit full.

4.3 Checking the Coalescer Assembly

- 4.3.1 Coalescers, where fitted, may be cleaned periodically to maintain efficiency. Coalescers should be checked following a major incident and replaced if necessary. Please contact us if you wish to purchase the coalescer media.
- 4.3.2 Identify the type and size of separator (shown on labels inside the access neck).

- 4.3.3 Assemblies weighing less than 25 Kg may be removed by hand. Heavier assemblies should be lifted by mechanical means. Any lifting device employed must be capable of lifting:
- 4.3.3.a In excess of the maximum assembly weight.
 - 4.3.3.b The assembly completely out of the access shaft.
 - 4.3.3.c Giving a smooth and controlled lift.
 - 4.3.3.d Swinging the assembly to one side clear of the access shaft.

Unit	Dry Weight (Kg)	Wet Weight (Kg)	Silted Weight (Kg)	Number Within unit	Replacement Media Part No.
NSBE010	5.7 kg	≈50 kg	≈60 kg	1	402862
NSBE015	6.2 kg	≈55 kg	≈65 kg	1	402864
NSBE020	6.2 kg	≈55 kg	≈65 kg	1	402864
NSBE025	12.0 kg	≈65 kg	≈75 kg	1	402866
NSBE030	12.0 kg	≈65 kg	≈75 kg	1	402866
NSBE036	14.0 kg	≈65 kg	≈75 kg	1	402718
NSBE040	21.0 kg	≈100 kg	≈200 kg	1	402885
NSBE050	21.0 kg	≈100 kg	≈200 kg	1	402885
NSBE075	21.0 kg	≈100 kg	≈200 kg	2	402885
NSBE100	21.0 kg	≈100 kg	≈200 kg	2	402885
NSBE125	21.0 kg	≈100 kg	≈200 kg	3	402885

- 4.3.4 Ensure that the area around the access shaft is clear and that there is space to place the assembly once removed. If space is not available it will be necessary to support the assembly over the access shaft. e.g. by scaffold poles and platform.
- 4.3.5 Only remove the access cover when necessary to remove the assembly. Do not leave the access shaft uncovered and unattended.

4.4 Removing the coalescer assembly.

- 4.4.1 Undo and remove the bracket which secures the coalescer to the access shaft.
- 4.4.2 Lift the assembly with a smooth and steady motion. Coalescers will become lighter as water drains from the exposed media. Allow the water to drain completely. Assemblies blocked with fine silt may be very heavy.
- 4.4.3 Fully extract the assembly and set it down adjacent to the access shaft.

4.5 Cleaning the coalescer assembly/ Media Replacement.

- 4.5.1 Hose down the assembly using clean water at normal pressure. If the media is heavily contaminated with oil and silt, it may not be possible to clean it effectively by hosing. Do not allow untreated cleaning water to pass out of the unit. Continue hosing until the water runs clear.
- 4.5.2 To replace the media, undo the banding. Slide media off the core tube and slide new media on. Ensure all the apertures on the core tube are covered by the media. Re-secure or replace banding. Consider replacing media and banding every two years.

4.6 Replacing the coalescer assembly.

- 4.6.1 Position it over the access shaft.
- 4.6.2 Lower the assembly steadily into the access shaft ensuring that the end locates within the sump at the bottom of the tank. Re-secure the bracket.
- 4.6.3 Replace the access cover.

5 Emergencies

- 5.1.1 At sites where there is a high risk of spillage, spill kits containing drain seals, absorbent materials, disposal containers and other appropriate equipment should be held. In the event of a spillage on site, the material should be contained, (if a spill kit is not available, sand or soil may be used) and the Environment Agency notified immediately using the appropriate emergency hotline number listed in the Agency Guideline PPG3. Year 2011 - **0800 80 70 60**

6 Warranty

The company will replace or, at its option, properly repair without charge any goods which are found to be defective and which cause failure in normal circumstances of use **within a period of twelve months from the date of delivery.**

This warranty is conditional upon:

- (a) the Buyer notifying the Company of any claim within Seven days of the failure becoming discernible.
- (b) the Company being allowed a reasonable opportunity to inspect the goods so as to confirm that they are defective.
- (c) the goods not having been modified, mishandled or misused and being used strictly in accordance with any relevant instructions issued by the Company.

The Company's liability under this Clause is limited to the repair or replacement of the defective goods, and does not cover costs of transport, installation or associated site costs, if applicable.

The Company's liability to replace or repair the goods is in lieu of and excludes all other warranties and conditions, and in particular (but without limitation) the Company shall have no liability of any kind for consequential loss or damage.

For any further advice, please us.

A warranty form is included in this package, to register your unit for warranty. Please complete ALL sections of the form, and return it at your earliest convenience.



Site address/location

Separator location

Type of separator
Nominal Flow
Total capacity

[illegible]

PRODUCT INFORMATION SHEET

AquaCell Plus-R

Description

Plus has been designed primarily for use in applications where inspectability is required, and is suitable for use in all applications from landscaped areas to heavily trafficked areas



Technical specification

Cat code	6LB250	Void ratio	95%
Colour	Black	Material	Recycled PP
Dimensions	1m x 0.5m x 0.4m	Vertical loading	70.2 tonnes/m ² (702 kN/m ²)
Weight	12.7kg	Lateral loading	15.1 tonnes/m ² (151 kN/m ²)
Storage volume	190 litres		

Maximum installation depths

Typical soil type	Maximum depth of installation – to base of units (m) ¹				
	Soil weight kN/m ³	Angle of internal friction φ (degrees) ^{2, 3}	Landscaped areas	Vehicle mass <9 tonnes ^{4, 5}	Vehicle mass <44 tonnes
Over consolidated stiff clay	20	24	4.67	4.42	4.17
Silty sandy clay	19	26	5.03	4.78	4.53
Loose sand and gravel	18	30	5.86	5.61	5.36
Medium dense sand and gravel	19	34	6.87	6.62	6.37
Dense sand and gravel	20	38	7.82	7.57	7.30

Minimum cover depths

	Landscaped areas	Car parks with vehicle mass <3 tonnes ⁵	Car parks with vehicle mass <9 tonnes	Car parks with vehicle mass <12 tonnes	Low speed roads with vehicle mass <60 tonnes
Minimum cover depth (m)	0.30	0.50	0.69	0.81	1.30

- Without groundwater present below base of units – AquaCell Plus-R may be used where groundwater is present, contact Wavin for technical advice.
- Loosening of dense sand or softening of clay by water can occur during installation. The designer should allow for any such likely effects when choosing an appropriate value of φ.
- The design is very sensitive to small changes in the assumed value of φ, therefore, it should be confirmed by a chartered geotechnical engineer. In clay soils, it may be possible to utilise cohesion in some cases.
- Applicable for car parks or other areas trafficked only by cars or occasional refuse collection trucks or similar vehicles (typically one per week).
- This category should be used when considering landscaped areas that may be trafficked by ride on mowers.

Assumptions made:

- Ground surface is horizontal
- Shear planes or other weaknesses are not present within the structure of the soil

Orders

0844 856 5152

Technical Advice

0844 856 5165

Email


technical.design@wavin.co.uk

Website

aquacell.wavin.co.uk

Appendix E

Storm Water Design Report

Malachy Walsh & Partners		Page 1
Mahon Technology Park Blackrock Cork		
Date 29/08/2023 10:48 File Cloonmore drainage Stor...	Designed by smoriarty Checked by	
XP Solutions	Network 2020.1.3	

STORM SEWER DESIGN by the Modified Rational Method

Design Criteria for Storm

Pipe Sizes STANDARD Manhole Sizes STANDARD









FSR Rainfall Model - Scotland and Ireland

Return Period (years)	30	PIMP (%)	100
M5-60 (mm)	18.400	Add Flow / Climate Change (%)	0
Ratio R	0.278	Minimum Backdrop Height (m)	0.200
Maximum Rainfall (mm/hr)	50	Maximum Backdrop Height (m)	1.500
Maximum Time of Concentration (mins)	30	Min Design Depth for Optimisation (m)	1.200
Foul Sewage (l/s/ha)	0.000	Min Vel for Auto Design only (m/s)	1.00
Volumetric Runoff Coeff.	0.750	Min Slope for Optimisation (1:X)	500

Designed with Level Soffits


Network Design Table for Storm

« - Indicates pipe capacity < flow

PN	Length (m)	Fall (m)	Slope (1:X)	I.Area (ha)	T.E. (mins)	Base Flow (l/s)	k (mm)	HYD SECT	DIA (mm)	Section Type	Auto Design
S1.000	40.726	0.136	299.5	0.181	5.00	0.0	0.600	o	300	Pipe/Conduit	
S1.001	5.796	0.020	289.8	0.000	0.00	0.0	0.600	o	375	Pipe/Conduit	
S1.002	5.796	0.020	289.8	0.018	0.00	0.0	0.600	o	375	Pipe/Conduit	
S1.003	41.725	0.083	502.7	0.007	0.00	0.0	0.600	o	375	Pipe/Conduit	
S1.004	10.610	0.035	303.1	0.000	0.00	0.0	0.600	o	375	Pipe/Conduit	
S2.000	7.802	0.035	222.9	0.000	5.00	0.0	0.600	o	225	Pipe/Conduit	
S3.000	54.176	0.181	299.3	0.172	5.00	0.0	0.600	o	300	Pipe/Conduit	
S1.005	4.816	0.013	370.5	0.000	0.00	0.0	0.600	o	375	Pipe/Conduit	


















Network Results Table

PN	Rain (mm/hr)	T.C. (mins)	US/IL Σ (m)	I.Area (ha)	Σ Base Flow (l/s)	Foul (l/s)	Add Flow (l/s)	Vel (m/s)	Cap (l/s)	Flow (l/s)
S1.000	50.00	5.75	6.465	0.181	0.0	0.0	0.0	0.90	63.9	24.5
S1.001	50.00	5.84	6.329	0.181	0.0	0.0	0.0	1.06	117.0	24.5
S1.002	50.00	5.93	6.209	0.199	0.0	0.0	0.0	1.06	117.0	26.9
S1.003	50.00	6.80	6.189	0.206	0.0	0.0	0.0	0.80	88.5	27.9
S1.004	50.00	6.97	6.106	0.206	0.0	0.0	0.0	1.04	114.4	27.9
S2.000	50.00	5.15	6.106	0.000	0.0	0.0	0.0	0.87	34.7	0.0
S3.000	50.00	6.00	6.252	0.172	0.0	0.0	0.0	0.90	63.9	23.3
S1.005	50.00	7.06	6.071	0.378	0.0	0.0	0.0	0.94	103.3	51.2

Malachy Walsh & Partners		Page 2
Mahon Technology Park Blackrock Cork		
Date 29/08/2023 10:48 File Cloonmore drainage Stor...	Designed by smoriarty Checked by	
XP Solutions Network 2020.1.3		


Network 2020.1.3

Network Design Table for Storm






PN	Length (m)	Fall (m)	Slope (1:X)	I.Area (ha)	T.E. (mins)	Base Flow (l/s)	k (mm)	HYD SECT	DIA (mm)	Section Type	Auto Design
S1.006	4.816	0.013	370.5	0.000	0.00	0.0	0.600	o	375	Pipe/Conduit	
S1.007	42.763	0.114	375.1	0.032	0.00	0.0	0.600	o	375	Pipe/Conduit	
S1.008	11.059	0.025	442.4	0.044	0.00	0.0	0.600	o	450	Pipe/Conduit	
S1.009	10.099	0.074	136.5	0.000	0.00	0.0	0.600	o	450	Pipe/Conduit	
S4.000	34.533	0.069	500.5	0.000	5.00	0.0	0.600	o	225	Pipe/Conduit	
S4.001	4.843	0.022	220.1	0.000	0.00	0.0	0.600	o	225	Pipe/Conduit	
S5.000	34.294	0.069	497.0	0.000	5.00	0.0	0.600	o	225	Pipe/Conduit	
S5.001	6.172	0.061	101.2	0.000	0.00	0.0	0.600	o	225	Pipe/Conduit	
S1.010	56.274	0.074	760.5	0.187	0.00	0.0	0.600	o	450	Pipe/Conduit	
S6.000	36.167	0.121	298.9	0.076	5.00	0.0	0.600	o	300	Pipe/Conduit	
S6.001	27.104	0.090	301.2	0.031	0.00	0.0	0.600	o	300	Pipe/Conduit	
S6.002	10.894	0.036	302.6	0.000	0.00	0.0	0.600	o	300	Pipe/Conduit	
S6.003	23.493	0.078	301.2	0.047	0.00	0.0	0.600	o	300	Pipe/Conduit	
S6.004	26.754	0.089	300.6	0.008	0.00	0.0	0.600	o	300	Pipe/Conduit	
S6.005	10.116	0.034	297.5	0.000	0.00	0.0	0.600	o	300	Pipe/Conduit	
S1.011	6.325	0.014	451.8	0.000	0.00	0.0	0.600	o	450	Pipe/Conduit	
S1.012	6.325	0.014	451.8	0.000	0.00	0.0	0.600	o	450	Pipe/Conduit	

Network Results Table

PN	Rain (mm/hr)	T.C. (mins)	US/IL (m)	I.Area (ha)	Base Flow (l/s)	Foul (l/s)	Add Flow (l/s)	Vel (m/s)	Cap (l/s)	Flow (l/s)
S1.006	50.00	7.14	5.958	0.378	0.0	0.0	0.0	0.94	103.3	51.2
S1.007	50.00	7.91	5.945	0.410	0.0	0.0	0.0	0.93	102.7	55.6
S1.008	50.00	8.10	5.831	0.454	0.0	0.0	0.0	0.96	152.7	61.5
S1.009	50.00	8.20	5.806	0.454	0.0	0.0	0.0	1.74	276.5	61.5
S4.000	50.00	6.00	6.800	0.000	0.0	0.0	0.0	0.58	23.0	0.0
S4.001	50.00	6.09	5.755	0.000	0.0	0.0	0.0	0.88	34.9	0.0
S5.000	50.00	5.99	6.800	0.000	0.0	0.0	0.0	0.58	23.1	0.0
S5.001	50.00	6.06	6.000	0.000	0.0	0.0	0.0	1.30	51.7	0.0
S1.010	50.00	9.49	5.733	0.642	0.0	0.0	0.0	0.73	116.0	86.9
S6.000	50.00	5.67	6.472	0.076	0.0	0.0	0.0	0.90	63.9	10.3
S6.001	50.00	6.17	6.351	0.107	0.0	0.0	0.0	0.90	63.7	14.5
S6.002	50.00	6.37	6.261	0.107	0.0	0.0	0.0	0.90	63.5	14.5
S6.003	50.00	6.80	6.225	0.153	0.0	0.0	0.0	0.90	63.7	20.8
S6.004	50.00	7.30	6.147	0.162	0.0	0.0	0.0	0.90	63.7	21.9
S6.005	50.00	7.49	6.058	0.162	0.0	0.0	0.0	0.91	64.1	21.9
S1.011	50.00	9.60	5.659	0.803	0.0	0.0	0.0	0.95	151.1	108.8
S1.012	50.00	9.71	5.545	0.803	0.0	0.0	0.0	0.95	151.1	108.8


Malachy Walsh & Partners		Page 3
Mahon Technology Park Blackrock Cork		
Date 29/08/2023 10:48 File Cloonmore drainage Stor...	Designed by smoriarty Checked by	
XP Solutions	Network 2020.1.3	


Network Design Table for Storm

PN	Length (m)	Fall (m)	Slope (1:X)	I.Area (ha)	T.E. (mins)	Base Flow (l/s)	k (mm)	HYD SECT	DIA (mm)	Section Type	Auto Design
S1.013	44.315	0.089	497.9	0.000	0.00	0.0	0.600	o	450	Pipe/Conduit	
S1.014	29.291	0.293	100.0	0.000	0.00	0.0	0.600	o	150	Pipe/Conduit	
S7.000	71.533	0.318	224.9	0.150	5.00	0.0	0.600	o	300	Pipe/Conduit	
S7.001	4.211	0.019	221.6	0.000	0.00	0.0	0.600	o	300	Pipe/Conduit	
S7.002	71.286	0.143	498.5	0.000	0.00	0.0	0.600	o	150	Pipe/Conduit	


Network Results Table


PN	Rain (mm/hr)	T.C. (mins)	US/IL (m)	Σ I.Area (ha)	Σ Base Flow (l/s)	Foul (l/s)	Add Flow (l/s)	Vel (m/s)	Cap (l/s)	Flow (l/s)
S1.013	50.00	10.52	5.531	0.803	0.0	0.0	0.0	0.90	143.8	108.8
S1.014	50.00	11.01	7.200	0.803	0.0	0.0	0.0	1.00	17.8«	108.8
S7.000	50.00	6.14	6.800	0.150	0.0	0.0	0.0	1.04	73.8	20.3
S7.001	50.00	6.21	6.482	0.150	0.0	0.0	0.0	1.05	74.4	20.3
S7.002	50.00	8.89	7.500	0.150	0.0	0.0	0.0	0.44	7.8«	20.3

Malachy Walsh & Partners								Page 4			
Mahon Technology Park Blackrock Cork											
Date 29/08/2023 10:48 File Cloonmore drainage Stor...				Designed by smoriarty Checked by							
XP Solutions				Network 2020.1.3							
Manhole Schedules for Storm											
MH Name	MH CL (m)	MH Depth (m)	MH Connection	MH Diam., L*W (mm)	PN	Pipe Out Invert Level (m)	Diameter (mm)	PN	Pipes In Invert Level (m)	Diameter (mm)	Backdrop (mm)
S1	7.550	1.085	Open Manhole	1200	S1.000	6.465	300				
S2	7.686	1.357	Open Manhole	1350	S1.001	6.329	375	S1.000	6.329	300	
S3	7.726	1.517	Open Manhole	1350	S1.002	6.209	375	S1.001	6.309	375	100
S4	7.730	1.541	Open Manhole	1350	S1.003	6.189	375	S1.002	6.189	375	
S5	7.728	1.622	Open Manhole	1350	S1.004	6.106	375	S1.003	6.106	375	
S6	7.758	1.652	Open Manhole	1200	S2.000	6.106	225				
S7	7.670	1.418	Open Manhole	1200	S3.000	6.252	300				
S8	7.662	1.591	Open Manhole	1350	S1.005	6.071	375	S1.004	6.071	375	
								S2.000	6.071	225	
								S3.000	6.071	300	
S9	7.783	1.825	Open Manhole	1350	S1.006	5.958	375	S1.005	6.058	375	100
S10	7.961	2.016	Open Manhole	1350	S1.007	5.945	375	S1.006	5.945	375	
S11	7.939	2.108	Open Manhole	1350	S1.008	5.831	450	S1.007	5.831	375	
S12	7.694	1.888	Open Manhole	1350	S1.009	5.806	450	S1.008	5.806	450	
S13	7.807	1.007	Open Manhole	1200	S4.000	6.800	225				
S14	7.625	1.870	Open Manhole	1200	S4.001	5.755	225	S4.000	6.731	225	976
S15	7.803	1.003	Open Manhole	1200	S5.000	6.800	225				
S16	7.758	1.758	Open Manhole	1200	S5.001	6.000	225	S5.000	6.731	225	731
S17	7.607	1.875	Open Manhole	1350	S1.010	5.733	450	S1.009	5.732	450	
								S4.001	5.733	225	
								S5.001	5.939	225	
S18	7.525	1.053	Open Manhole	1200	S6.000	6.472	300				
S19	7.428	1.077	Open Manhole	1200	S6.001	6.351	300	S6.000	6.351	300	
S20	7.535	1.274	Open Manhole	1200	S6.002	6.261	300	S6.001	6.261	300	
S21	7.462	1.237	Open Manhole	1200	S6.003	6.225	300	S6.002	6.225	300	
S22	7.544	1.397	Open Manhole	1200	S6.004	6.147	300	S6.003	6.147	300	
S23	7.347	1.289	Open Manhole	1200	S6.005	6.058	300	S6.004	6.058	300	
S24	7.670	2.011	Open Manhole	1350	S1.011	5.659	450	S1.010	5.659	450	
								S6.005	6.024	300	215
S25	7.829	2.284	Open Manhole	1350	S1.012	5.545	450	S1.011	5.645	450	100
S26	7.794	2.263	Open Manhole	1350	S1.013	5.531	450	S1.012	5.531	450	
S27	7.587	2.145	Open Manhole	1350	S1.014	7.200	150	S1.013	5.442	450	
S	7.274	0.367	Open Manhole	0		OUTFALL		S1.014	6.907	150	
S28	7.824	1.024	Open Manhole	1200	S7.000	6.800	300				
S29	7.827	1.345	Open Manhole	1200	S7.001	6.482	300	S7.000	6.482	300	
S30	7.833	1.370	Open Manhole	1200	S7.002	7.500	150	S7.001	6.463	300	
S	7.550	0.193	Open Manhole	0		OUTFALL		S7.002	7.357	150	
©1982-2020 Innovyze											

Malachy Walsh & Partners		Page 7
Mahon Technology Park Blackrock Cork		
Date 29/08/2023 10:48 File Cloonmore drainage Stor...	Designed by smoriarty Checked by	
XP Solutions	Network 2020.1.3	

Manhole Schedules for Storm

MH Name	Manhole Easting (m)	Manhole Northing (m)	Intersection Easting (m)	Intersection Northing (m)	Manhole Access	Layout (North)
S30	484626.702	614184.959	484626.702	614184.959	Required	
S	484558.750	614163.416			No Entry	

Malachy Walsh & Partners		Page 8
Mahon Technology Park Blackrock Cork		
Date 29/08/2023 10:48 File Cloonmore drainage Stor...	Designed by smoriarty Checked by	
XP Solutions	Network 2020.1.3	


PIPELINE SCHEDULES for Storm

Upstream Manhole

PN	Hyd Sect	Diam (mm)	MH Name	C.Level (m)	I.Level (m)	D.Depth (m)	MH Connection	MH DIAM., L*W (mm)
S1.000	o	300	S1	7.550	6.465	0.785	Open Manhole	1200
S1.001	o	375	S2	7.686	6.329	0.982	Open Manhole	1350
S1.002	o	375	S3	7.726	6.209	1.142	Open Manhole	1350
S1.003	o	375	S4	7.730	6.189	1.166	Open Manhole	1350
S1.004	o	375	S5	7.728	6.106	1.247	Open Manhole	1350
S2.000	o	225	S6	7.758	6.106	1.427	Open Manhole	1200
S3.000	o	300	S7	7.670	6.252	1.118	Open Manhole	1200
S1.005	o	375	S8	7.662	6.071	1.216	Open Manhole	1350
S1.006	o	375	S9	7.783	5.958	1.450	Open Manhole	1350
S1.007	o	375	S10	7.961	5.945	1.641	Open Manhole	1350
S1.008	o	450	S11	7.939	5.831	1.658	Open Manhole	1350
S1.009	o	450	S12	7.694	5.806	1.438	Open Manhole	1350
S4.000	o	225	S13	7.807	6.800	0.782	Open Manhole	1200
S4.001	o	225	S14	7.625	5.755	1.645	Open Manhole	1200
S5.000	o	225	S15	7.803	6.800	0.778	Open Manhole	1200
S5.001	o	225	S16	7.758	6.000	1.533	Open Manhole	1200

Downstream Manhole

PN	Length (m)	Slope (1:X)	MH Name	C.Level (m)	I.Level (m)	D.Depth (m)	MH Connection	MH DIAM., L*W (mm)
S1.000	40.726	299.5	S2	7.686	6.329	1.057	Open Manhole	1350
S1.001	5.796	289.8	S3	7.726	6.309	1.042	Open Manhole	1350
S1.002	5.796	289.8	S4	7.730	6.189	1.166	Open Manhole	1350
S1.003	41.725	502.7	S5	7.728	6.106	1.247	Open Manhole	1350
S1.004	10.610	303.1	S8	7.662	6.071	1.216	Open Manhole	1350
S2.000	7.802	222.9	S8	7.662	6.071	1.366	Open Manhole	1350
S3.000	54.176	299.3	S8	7.662	6.071	1.291	Open Manhole	1350
S1.005	4.816	370.5	S9	7.783	6.058	1.350	Open Manhole	1350
S1.006	4.816	370.5	S10	7.961	5.945	1.641	Open Manhole	1350
S1.007	42.763	375.1	S11	7.939	5.831	1.733	Open Manhole	1350
S1.008	11.059	442.4	S12	7.694	5.806	1.438	Open Manhole	1350
S1.009	10.099	136.5	S17	7.607	5.732	1.425	Open Manhole	1350
S4.000	34.533	500.5	S14	7.625	6.731	0.669	Open Manhole	1200
S4.001	4.843	220.1	S17	7.607	5.733	1.649	Open Manhole	1350
S5.000	34.294	497.0	S16	7.758	6.731	0.802	Open Manhole	1200
S5.001	6.172	101.2	S17	7.607	5.939	1.443	Open Manhole	1350

Malachy Walsh & Partners		Page 9
Mahon Technology Park Blackrock Cork		
Date 29/08/2023 10:48 File Cloonmore drainage Stor...	Designed by smoriarty Checked by	
XP Solutions	Network 2020.1.3	


PIPELINE SCHEDULES for Storm

Upstream Manhole

PN	Hyd Sect	Diam (mm)	MH Name	C.Level (m)	I.Level (m)	D.Depth (m)	MH Connection	MH DIAM., L*W (mm)
S1.010	o	450	S17	7.607	5.733	1.424	Open Manhole	1350
S6.000	o	300	S18	7.525	6.472	0.753	Open Manhole	1200
S6.001	o	300	S19	7.428	6.351	0.777	Open Manhole	1200
S6.002	o	300	S20	7.535	6.261	0.974	Open Manhole	1200
S6.003	o	300	S21	7.462	6.225	0.937	Open Manhole	1200
S6.004	o	300	S22	7.544	6.147	1.097	Open Manhole	1200
S6.005	o	300	S23	7.347	6.058	0.989	Open Manhole	1200
S1.011	o	450	S24	7.670	5.659	1.561	Open Manhole	1350
S1.012	o	450	S25	7.829	5.545	1.834	Open Manhole	1350
S1.013	o	450	S26	7.794	5.531	1.813	Open Manhole	1350
S1.014	o	150	S27	7.587	7.200	0.237	Open Manhole	1350
S7.000	o	300	S28	7.824	6.800	0.724	Open Manhole	1200
S7.001	o	300	S29	7.827	6.482	1.045	Open Manhole	1200
S7.002	o	150	S30	7.833	7.500	0.183	Open Manhole	1200

Downstream Manhole

PN	Length (m)	Slope (1:X)	MH Name	C.Level (m)	I.Level (m)	D.Depth (m)	MH Connection	MH DIAM., L*W (mm)
S1.010	56.274	760.5	S24	7.670	5.659	1.561	Open Manhole	1350
S6.000	36.167	298.9	S19	7.428	6.351	0.777	Open Manhole	1200
S6.001	27.104	301.2	S20	7.535	6.261	0.974	Open Manhole	1200
S6.002	10.894	302.6	S21	7.462	6.225	0.937	Open Manhole	1200
S6.003	23.493	301.2	S22	7.544	6.147	1.097	Open Manhole	1200
S6.004	26.754	300.6	S23	7.347	6.058	0.989	Open Manhole	1200
S6.005	10.116	297.5	S24	7.670	6.024	1.346	Open Manhole	1350
S1.011	6.325	451.8	S25	7.829	5.645	1.734	Open Manhole	1350
S1.012	6.325	451.8	S26	7.794	5.531	1.813	Open Manhole	1350
S1.013	44.315	497.9	S27	7.587	5.442	1.695	Open Manhole	1350
S1.014	29.291	100.0	S	7.274	6.907	0.217	Open Manhole	0
S7.000	71.533	224.9	S29	7.827	6.482	1.045	Open Manhole	1200
S7.001	4.211	221.6	S30	7.833	6.463	1.070	Open Manhole	1200
S7.002	71.286	498.5	S	7.550	7.357	0.043	Open Manhole	0

Malachy Walsh & Partners		Page 10
Mahon Technology Park Blackrock Cork		
Date 29/08/2023 10:48 File Cloonmore drainage Stor...	Designed by smoriarty Checked by	
XP Solutions	Network 2020.1.3	

Free Flowing Outfall Details for Storm

Outfall Pipe Number	Outfall Name	C. Level (m)	I. Level (m)	Min I. Level (m)	D,L (mm)	W (mm)
------------------------	-----------------	-----------------	-----------------	------------------------	-------------	-----------

S1.014	S	7.274	6.907	0.000	0	0
--------	---	-------	-------	-------	---	---

Free Flowing Outfall Details for Storm

Outfall Pipe Number	Outfall Name	C. Level (m)	I. Level (m)	Min I. Level (m)	D,L (mm)	W (mm)
------------------------	-----------------	-----------------	-----------------	------------------------	-------------	-----------

S7.002	S	7.550	7.357	0.000	0	0
--------	---	-------	-------	-------	---	---


Simulation Criteria for Storm


Volumetric Runoff Coeff	0.750	Additional Flow - % of Total Flow	0.000
Areal Reduction Factor	1.000	MADD Factor * 10m ³ /ha Storage	2.000
Hot Start (mins)	0	Inlet Coefficient	0.800
Hot Start Level (mm)	0	Flow per Person per Day (l/per/day)	0.000
Manhole Headloss Coeff (Global)	0.500	Run Time (mins)	60
Foul Sewage per hectare (l/s)	0.000	Output Interval (mins)	1


Number of Input Hydrographs	0	Number of Storage Structures	6
Number of Online Controls	0	Number of Time/Area Diagrams	0
Number of Offline Controls	0	Number of Real Time Controls	0

Synthetic Rainfall Details

Rainfall Model	FSR	Profile Type	Summer
Return Period (years)	30	Cv (Summer)	0.750
Region	Scotland and Ireland	Cv (Winter)	0.840
M5-60 (mm)	18.400	Storm Duration (mins)	30
Ratio R	0.278		

Malachy Walsh & Partners		Page 11																																																																								
Mahon Technology Park Blackrock Cork																																																																										
Date 29/08/2023 10:48 File Cloonmore drainage Stor...	Designed by smoriarty Checked by																																																																									
XP Solutions	Network 2020.1.3																																																																									
<div>Storage Structures for Storm</div> <div>Cellular Storage Manhole: S5, DS/PN: S1.004</div> <div>Invert Level (m) 5.442 Safety Factor 2.0 Infiltration Coefficient Base (m/hr) 0.00180 Porosity 0.95 Infiltration Coefficient Side (m/hr) 0.00180</div> <table><tr><th>Depth (m)</th><th>Area (m²)</th><th>Inf. Area (m²)</th><th>Depth (m)</th><th>Area (m²)</th><th>Inf. Area (m²)</th></tr><tr><td>0.000</td><td>250.0</td><td>250.0</td><td>1.100</td><td>0.0</td><td>360.0</td></tr><tr><td>1.000</td><td>250.0</td><td>360.0</td><td></td><td></td><td></td></tr></table> <div>Cellular Storage Manhole: S11, DS/PN: S1.008</div> <div>Invert Level (m) 5.442 Safety Factor 2.0 Infiltration Coefficient Base (m/hr) 0.00002 Porosity 0.95 Infiltration Coefficient Side (m/hr) 0.00002</div> <table><tr><th>Depth (m)</th><th>Area (m²)</th><th>Inf. Area (m²)</th><th>Depth (m)</th><th>Area (m²)</th><th>Inf. Area (m²)</th></tr><tr><td>0.000</td><td>600.0</td><td>600.0</td><td>1.100</td><td>0.0</td><td>710.0</td></tr><tr><td>1.000</td><td>600.0</td><td>710.0</td><td></td><td></td><td></td></tr></table> <div>Cellular Storage Manhole: S14, DS/PN: S4.001</div> <div>Invert Level (m) 5.775 Safety Factor 2.0 Infiltration Coefficient Base (m/hr) 0.00000 Porosity 0.95 Infiltration Coefficient Side (m/hr) 0.00000</div> <table><tr><th>Depth (m)</th><th>Area (m²)</th><th>Inf. Area (m²)</th><th>Depth (m)</th><th>Area (m²)</th><th>Inf. Area (m²)</th></tr><tr><td>0.000</td><td>80.0</td><td>0.0</td><td>1.201</td><td>0.0</td><td>0.0</td></tr><tr><td>1.200</td><td>80.0</td><td>0.0</td><td></td><td></td><td></td></tr></table> <div>Cellular Storage Manhole: S16, DS/PN: S5.001</div> <div>Invert Level (m) 6.000 Safety Factor 2.0 Infiltration Coefficient Base (m/hr) 0.00000 Porosity 0.95 Infiltration Coefficient Side (m/hr) 0.00000</div> <table><tr><th>Depth (m)</th><th>Area (m²)</th><th>Inf. Area (m²)</th><th>Depth (m)</th><th>Area (m²)</th><th>Inf. Area (m²)</th></tr><tr><td>0.000</td><td>80.0</td><td>0.0</td><td>1.201</td><td>0.0</td><td>0.0</td></tr><tr><td>1.200</td><td>80.0</td><td>0.0</td><td></td><td></td><td></td></tr></table> <div>Cellular Storage Manhole: S27, DS/PN: S1.014</div> <div>Invert Level (m) 5.442 Safety Factor 2.0 Infiltration Coefficient Base (m/hr) 0.00002 Porosity 0.95 Infiltration Coefficient Side (m/hr) 0.00002</div>			Depth (m)	Area (m²)	Inf. Area (m²)	Depth (m)	Area (m²)	Inf. Area (m²)	0.000	250.0	250.0	1.100	0.0	360.0	1.000	250.0	360.0				Depth (m)	Area (m²)	Inf. Area (m²)	Depth (m)	Area (m²)	Inf. Area (m²)	0.000	600.0	600.0	1.100	0.0	710.0	1.000	600.0	710.0				Depth (m)	Area (m²)	Inf. Area (m²)	Depth (m)	Area (m²)	Inf. Area (m²)	0.000	80.0	0.0	1.201	0.0	0.0	1.200	80.0	0.0				Depth (m)	Area (m²)	Inf. Area (m²)	Depth (m)	Area (m²)	Inf. Area (m²)	0.000	80.0	0.0	1.201	0.0	0.0	1.200	80.0	0.0			
Depth (m)	Area (m²)	Inf. Area (m²)	Depth (m)	Area (m²)	Inf. Area (m²)																																																																					
0.000	250.0	250.0	1.100	0.0	360.0																																																																					
1.000	250.0	360.0																																																																								
Depth (m)	Area (m²)	Inf. Area (m²)	Depth (m)	Area (m²)	Inf. Area (m²)																																																																					
0.000	600.0	600.0	1.100	0.0	710.0																																																																					
1.000	600.0	710.0																																																																								
Depth (m)	Area (m²)	Inf. Area (m²)	Depth (m)	Area (m²)	Inf. Area (m²)																																																																					
0.000	80.0	0.0	1.201	0.0	0.0																																																																					
1.200	80.0	0.0																																																																								
Depth (m)	Area (m²)	Inf. Area (m²)	Depth (m)	Area (m²)	Inf. Area (m²)																																																																					
0.000	80.0	0.0	1.201	0.0	0.0																																																																					
1.200	80.0	0.0																																																																								
©1982-2020 Innovyze																																																																										


Malachy Walsh & Partners		Page 12																																				
Mahon Technology Park Blackrock Cork																																						
Date 29/08/2023 10:48 File Cloonmore drainage Stor...	Designed by smoriarty Checked by																																					
XP Solutions Network 2020.1.3																																						
<p><u>Cellular Storage Manhole: S27, DS/PN: S1.014</u></p> <table><thead><tr><th>Depth (m)</th><th>Area (m²)</th><th>Inf. Area (m²)</th><th>Depth (m)</th><th>Area (m²)</th><th>Inf. Area (m²)</th></tr></thead><tbody><tr><td>0.000</td><td>336.0</td><td>336.0</td><td>1.100</td><td>0.0</td><td>436.0</td></tr><tr><td>1.000</td><td>336.0</td><td>436.0</td><td></td><td></td><td></td></tr></tbody></table> <p><u>Cellular Storage Manhole: S30, DS/PN: S7.002</u></p> <p>Invert Level (m) 6.463 Safety Factor 2.0 Infiltration Coefficient Base (m/hr) 0.00007 Porosity 0.95 Infiltration Coefficient Side (m/hr) 0.00007</p> <table><thead><tr><th>Depth (m)</th><th>Area (m²)</th><th>Inf. Area (m²)</th><th>Depth (m)</th><th>Area (m²)</th><th>Inf. Area (m²)</th></tr></thead><tbody><tr><td>0.000</td><td>250.0</td><td>250.0</td><td>1.100</td><td>0.0</td><td>360.0</td></tr><tr><td>1.000</td><td>250.0</td><td>360.0</td><td></td><td></td><td></td></tr></tbody></table>			Depth (m)	Area (m²)	Inf. Area (m²)	Depth (m)	Area (m²)	Inf. Area (m²)	0.000	336.0	336.0	1.100	0.0	436.0	1.000	336.0	436.0				Depth (m)	Area (m²)	Inf. Area (m²)	Depth (m)	Area (m²)	Inf. Area (m²)	0.000	250.0	250.0	1.100	0.0	360.0	1.000	250.0	360.0			
Depth (m)	Area (m²)	Inf. Area (m²)	Depth (m)	Area (m²)	Inf. Area (m²)																																	
0.000	336.0	336.0	1.100	0.0	436.0																																	
1.000	336.0	436.0																																				
Depth (m)	Area (m²)	Inf. Area (m²)	Depth (m)	Area (m²)	Inf. Area (m²)																																	
0.000	250.0	250.0	1.100	0.0	360.0																																	
1.000	250.0	360.0																																				
©1982-2020 Innovyze																																						

Malachy Walsh & Partners		Page 14
Mahon Technology Park Blackrock Cork		
Date 29/08/2023 10:48 File Cloonmore drainage Stor...	Designed by smoriarty Checked by	
XP Solutions	Network 2020.1.3	

1 year Return Period Summary of Critical Results by Maximum Level (Rank 1)
for Storm

PN	US/MH Name	Overflow Act.	Water Level	Surcharged Depth	Flooded Volume	Flow /	Overflow	Half Drain Time	Pipe Flow	Status
			(m)	(m)	(m³)	Cap.	(l/s)	(mins)	(l/s)	
S1.000	S1		6.609	-0.156	0.000	0.45			26.6	OK
S1.001	S2		6.483	-0.221	0.000	0.35			26.1	OK
S1.002	S3		6.369	-0.215	0.000	0.38			28.3	OK
S1.003	S4		6.344	-0.220	0.000	0.36			29.1	OK
S1.004	S5		6.021	-0.460	0.000	0.00			0.0	OK
S2.000	S6		6.203	-0.128	0.000	0.01			0.3	OK
S3.000	S7		6.390	-0.162	0.000	0.41			24.8	OK
S1.005	S8		6.204	-0.242	0.000	0.27			21.0	OK
S1.006	S9		6.091	-0.242	0.000	0.27			20.9	OK
S1.007	S10		6.075	-0.245	0.000	0.26			24.6	OK
S1.008	S11		5.978	-0.303	0.000	0.02			2.0	OK
S1.009	S12		5.983	-0.273	0.000	0.01			2.1	OK
S4.000	S13		6.800	-0.225	0.000	0.00			0.0	OK
S4.001	S14		5.979	-0.001	0.000	0.02			0.4	OK
S5.000	S15		6.800	-0.225	0.000	0.00			0.0	OK
S5.001	S16		6.000	-0.225	0.000	0.00			0.0	OK

PN	US/MH Name	Level Exceeded
S1.000	S1	
S1.001	S2	
S1.002	S3	
S1.003	S4	
S1.004	S5	
S2.000	S6	
S3.000	S7	
S1.005	S8	
S1.006	S9	
S1.007	S10	
S1.008	S11	
S1.009	S12	
S4.000	S13	
S4.001	S14	
S5.000	S15	
S5.001	S16	


Malachy Walsh & Partners		Page 15
Mahon Technology Park Blackrock Cork		
Date 29/08/2023 10:48	Designed by smoriarty	
File Cloonmore drainage Stor...	Checked by	
XP Solutions		Network 2020.1.3


1 year Return Period Summary of Critical Results by Maximum Level (Rank 1)
for Storm

PN	US/MH Name	Storm	Return Period	Climate Change	First (X) Surcharge	First (Y) Flood	First (Z) Overflow
S1.010	S17	10080 Winter	1	+20%	30/7200 Winter	100/8640 Summer	
S6.000	S18	15 Winter	1	+20%			
S6.001	S19	15 Winter	1	+20%			
S6.002	S20	15 Winter	1	+20%			
S6.003	S21	15 Winter	1	+20%			
S6.004	S22	15 Winter	1	+20%			
S6.005	S23	15 Winter	1	+20%	100/5760 Winter		
S1.011	S24	10080 Winter	1	+20%	30/4320 Winter		
S1.012	S25	10080 Winter	1	+20%	30/2160 Winter		
S1.013	S26	10080 Winter	1	+20%	1/10080 Winter		
S1.014	S27	10080 Winter	1	+20%			
S7.000	S28	10080 Winter	1	+20%	30/4320 Winter		
S7.001	S29	10080 Winter	1	+20%	1/2880 Winter		
S7.002	S30	10080 Winter	1	+20%			

PN	US/MH Name	Overflow Act.	Water Level (m)	Surcharged Depth (m)	Flooded Volume (m³)	Flow / Cap.	Overflow (l/s)	Half Drain Time (mins)	Pipe Flow (l/s)
S1.010	S17		5.984	-0.199	0.000	0.02			2.5
S6.000	S18		6.562	-0.210	0.000	0.19			11.2
S6.001	S19		6.455	-0.196	0.000	0.26			14.8
S6.002	S20		6.378	-0.183	0.000	0.29			14.6
S6.003	S21		6.348	-0.177	0.000	0.35			19.7
S6.004	S22		6.271	-0.176	0.000	0.35			20.3
S6.005	S23		6.190	-0.168	0.000	0.40			20.3
S1.011	S24		5.981	-0.128	0.000	0.02			2.1
S1.012	S25		5.983	-0.012	0.000	0.02			2.4
S1.013	S26		5.985	0.004	0.000	0.02			2.2
S1.014	S27		5.984	-1.366	0.000	0.00			0.0
S7.000	S28		6.968	-0.132	0.000	0.01			0.5
S7.001	S29		6.968	0.186	0.000	0.01			0.5
S7.002	S30		6.968	-0.682	0.000	0.00			0.0

PN	US/MH Name	Status	Level Exceeded
S1.010	S17	OK	
S6.000	S18	OK	
S6.001	S19	OK	
S6.002	S20	OK	
S6.003	S21	OK	
S6.004	S22	OK	
S6.005	S23	OK	
S1.011	S24	OK	


Malachy Walsh & Partners		Page 16
Mahon Technology Park Blackrock Cork		
Date 29/08/2023 10:48	Designed by smoriarty	
File Cloonmore drainage Stor...	Checked by	
XP Solutions	Network 2020.1.3	
<u>1 year Return Period Summary of Critical Results by Maximum Level (Rank 1)</u> <u>for Storm</u>		
	<div><div>US/MH</div><div><div>PN</div><div>Name</div><div>Status</div><div>Level Exceeded</div></div></div>	
S1.012	S25	OK
S1.013	S26	SURCHARGED
S1.014	S27	OK
S7.000	S28	OK
S7.001	S29	SURCHARGED
S7.002	S30	OK
©1982-2020 Innovyze		

Malachy Walsh & Partners		Page 18
Mahon Technology Park Blackrock Cork		
Date 29/08/2023 10:48 File Cloonmore drainage Stor...	Designed by smoriarty Checked by	
XP Solutions	Network 2020.1.3	

30 year Return Period Summary of Critical Results by Maximum Level (Rank 1)
for Storm

PN	US/MH Name	Overflow Act.	Water Surcharged Flooded			Flow / Overflow Cap. (l/s)	Half Drain Time (mins)	Pipe Flow (l/s)
			Level (m)	Depth (m)	Volume (m³)			
S1.000	S1		6.727	-0.038	0.000	0.98		58.4
S1.001	S2		6.579	-0.125	0.000	0.78		57.9
S1.002	S3		6.474	-0.110	0.000	0.83		62.2
S1.003	S4		6.442	-0.122	0.000	0.79		63.8
S1.004	S5		6.269	-0.212	0.000	0.03		2.7
S2.000	S6		6.274	-0.057	0.000	0.01		0.4
S3.000	S7		6.487	-0.065	0.000	0.91		55.2
S1.005	S8		6.274	-0.172	0.000	0.57		43.9
S1.006	S9		6.269	-0.064	0.000	0.04		3.1
S1.007	S10		6.269	-0.051	0.000	0.04		3.3
S1.008	S11		6.270	-0.011	0.000	0.10		9.0
S1.009	S12		6.324	0.068	0.000	0.04		7.3
S4.000	S13		6.800	-0.225	0.000	0.00		0.0
S4.001	S14		6.270	0.290	0.000	0.05		1.3
S5.000	S15		6.800	-0.225	0.000	0.00		0.0
S5.001	S16		6.270	0.045	0.000	0.04		1.3

PN	US/MH Name	Status	Level Exceeded
S1.000	S1	OK	
S1.001	S2	OK	
S1.002	S3	OK	
S1.003	S4	OK	
S1.004	S5	OK	
S2.000	S6	OK	
S3.000	S7	OK	
S1.005	S8	OK	
S1.006	S9	OK	
S1.007	S10	OK	
S1.008	S11	OK	
S1.009	S12	SURCHARGED	
S4.000	S13	OK	
S4.001	S14	SURCHARGED	
S5.000	S15	OK	
S5.001	S16	SURCHARGED	


Malachy Walsh & Partners		Page 19
Mahon Technology Park Blackrock Cork		
Date 29/08/2023 10:48	Designed by smoriarty	
File Cloonmore drainage Stor...	Checked by	
XP Solutions		Network 2020.1.3


30 year Return Period Summary of Critical Results by Maximum Level (Rank 1)
for Storm

PN	US/MH Name	Storm	Return Period	Climate Change	First (X) Surcharge	First (Y) Flood	First (Z) Overflow
S1.010	S17	10080 Winter	30	+20%	30/7200 Winter	100/8640 Summer	
S6.000	S18	15 Winter	30	+20%			
S6.001	S19	15 Winter	30	+20%			
S6.002	S20	15 Winter	30	+20%			
S6.003	S21	15 Winter	30	+20%			
S6.004	S22	15 Winter	30	+20%			
S6.005	S23	10080 Winter	30	+20%	100/5760 Winter		
S1.011	S24	10080 Winter	30	+20%	30/4320 Winter		
S1.012	S25	10080 Winter	30	+20%	30/2160 Winter		
S1.013	S26	10080 Winter	30	+20%	1/10080 Winter		
S1.014	S27	10080 Winter	30	+20%			
S7.000	S28	10080 Winter	30	+20%	30/4320 Winter		
S7.001	S29	10080 Winter	30	+20%	1/2880 Winter		
S7.002	S30	10080 Winter	30	+20%			

PN	US/MH Name	Overflow Act.	Water Level (m)	Surcharged Depth (m)	Flooded Volume (m³)	Flow / Cap.	Overflow (l/s)	Half Drain Time (mins)	Pipe Flow (l/s)
S1.010	S17		6.315	0.132	0.000	0.07			7.2
S6.000	S18		6.611	-0.161	0.000	0.42			25.0
S6.001	S19		6.521	-0.130	0.000	0.59			33.8
S6.002	S20		6.461	-0.100	0.000	0.68			34.2
S6.003	S21		6.435	-0.090	0.000	0.81			45.8
S6.004	S22		6.356	-0.091	0.000	0.81			46.7
S6.005	S23		6.289	-0.069	0.000	0.02			0.9
S1.011	S24		6.290	0.181	0.000	0.07			7.3
S1.012	S25		6.298	0.303	0.000	0.07			7.1
S1.013	S26		6.297	0.316	0.000	0.05			6.8
S1.014	S27		6.296	-1.054	0.000	0.00			0.0
S7.000	S28		7.296	0.196	0.000	0.01			0.9
S7.001	S29		7.296	0.514	0.000	0.02			0.8
S7.002	S30		7.296	-0.354	0.000	0.00			0.0

PN	US/MH Name	Status	Level Exceeded
S1.010	S17	SURCHARGED	
S6.000	S18	OK	
S6.001	S19	OK	
S6.002	S20	OK	
S6.003	S21	OK	
S6.004	S22	OK	
S6.005	S23	OK	
S1.011	S24	SURCHARGED	

Malachy Walsh & Partners		Page 20
Mahon Technology Park Blackrock Cork		
Date 29/08/2023 10:48	Designed by smoriarty	
File Cloonmore drainage Stor...	Checked by	
XP Solutions	Network 2020.1.3	
<u>30 year Return Period Summary of Critical Results by Maximum Level (Rank 1)</u> <u>for Storm</u>		
	<div><div>US/MH</div><div>PN Name Status Level Exceeded</div></div>	
	S1.012 S25 SURCHARGED	
	S1.013 S26 SURCHARGED	
	S1.014 S27 OK	
	S7.000 S28 SURCHARGED	
	S7.001 S29 SURCHARGED	
	S7.002 S30 OK	
©1982-2020 Innovyze		

Malachy Walsh & Partners		Page 21
Mahon Technology Park Blackrock Cork		
Date 29/08/2023 10:48 File Cloonmore drainage Stor...	Designed by smoriarty Checked by	
XP Solutions	Network 2020.1.3	

100 year Return Period Summary of Critical Results by Maximum Level (Rank 1) for Storm

Simulation Criteria

Areal Reduction Factor 1.000 Additional Flow - % of Total Flow 0.000
 Hot Start (mins) 0 MADD Factor * 10m³/ha Storage 2.000
 Hot Start Level (mm) 0 Inlet Coefficient 0.800
 Manhole Headloss Coeff (Global) 0.500 Flow per Person per Day (l/per/day) 0.000
 Foul Sewage per hectare (l/s) 0.000

Number of Input Hydrographs 0 Number of Storage Structures 6
 Number of Online Controls 0 Number of Time/Area Diagrams 0
 Number of Offline Controls 0 Number of Real Time Controls 0

Synthetic Rainfall Details


Rainfall Model FSR Ratio R 0.278
 Region Scotland and Ireland Cv (Summer) 0.750
 M5-60 (mm) 18.400 Cv (Winter) 0.840

Margin for Flood Risk Warning (mm) 100.0 DVD Status OFF
 Analysis Timestep Fine Inertia Status OFF
 DTS Status ON

Profile(s) Summer and Winter
 Duration(s) (mins) 15, 30, 60, 120, 180, 240, 360, 480, 600,
 720, 960, 1440, 2160, 2880, 4320, 5760,
 7200, 8640, 10080
 Return Period(s) (years) 1, 30, 100
 Climate Change (%) 20, 20, 20

WARNING: Half Drain Time has not been calculated as the structure is too full.


PN	US/MH Name	Storm	Return Period	Climate Change	First (X) Surcharge	First (Y) Flood	First (Z) Overflow
S1.000	S1	15 Winter	100	+20%	100/15 Summer		
S1.001	S2	15 Winter	100	+20%			
S1.002	S3	15 Winter	100	+20%			
S1.003	S4	15 Winter	100	+20%			
S1.004	S5	10080 Winter	100	+20%			
S2.000	S6	10080 Winter	100	+20%	100/5760 Winter		
S3.000	S7	15 Winter	100	+20%	100/15 Summer		
S1.005	S8	10080 Winter	100	+20%			
S1.006	S9	10080 Winter	100	+20%	100/5760 Winter		
S1.007	S10	10080 Winter	100	+20%	100/5760 Winter		
S1.008	S11	10080 Winter	100	+20%	100/5760 Winter		
S1.009	S12	10080 Winter	100	+20%	30/8640 Winter	100/8640 Summer	
S4.000	S13	15 Summer	100	+20%			
S4.001	S14	8640 Winter	100	+20%	30/2160 Winter		
S5.000	S15	15 Summer	100	+20%			
S5.001	S16	10080 Winter	100	+20%	30/7200 Winter		

Malachy Walsh & Partners		Page 22
Mahon Technology Park Blackrock Cork		
Date 29/08/2023 10:48 File Cloonmore drainage Stor...	Designed by smoriarty Checked by	
XP Solutions	Network 2020.1.3	

100 year Return Period Summary of Critical Results by Maximum Level (Rank 1) for Storm

PN	US/MH Name	Overflow Act.	Water Surcharged Flooded				Half Drain Time (mins)	Pipe Flow (l/s)
			Level (m)	Depth (m)	Volume (m³)	Flow / Overflow Cap. (l/s)		
S1.000	S1		6.858	0.093	0.000	1.27		75.4
S1.001	S2		6.630	-0.074	0.000	1.00		74.4
S1.002	S3		6.584	0.000	0.000	1.05		78.6
S1.003	S4		6.500	-0.064	0.000	0.99		80.0
S1.004	S5		6.349	-0.132	0.000	0.02		1.4
S2.000	S6		6.350	0.019	0.000	0.00		0.0
S3.000	S7		6.639	0.087	0.000	1.17		70.6
S1.005	S8		6.350	-0.096	0.000	0.03		2.3
S1.006	S9		6.352	0.019	0.000	0.03		2.3
S1.007	S10		6.353	0.033	0.000	0.03		2.5
S1.008	S11		6.354	0.073	0.000	0.12		11.0
S1.009	S12		6.615	0.359	0.000	0.04		7.4
S4.000	S13		6.800	-0.225	0.000	0.00		0.0
S4.001	S14		6.375	0.395	0.000	0.07		1.8
S5.000	S15		6.800	-0.225	0.000	0.00		0.0
S5.001	S16		6.374	0.149	0.000	0.05		1.8

PN	US/MH Name	Status	Level Exceeded
S1.000	S1	SURCHARGED	
S1.001	S2	OK	
S1.002	S3	OK	
S1.003	S4	OK	
S1.004	S5	OK	
S2.000	S6	SURCHARGED	
S3.000	S7	SURCHARGED	
S1.005	S8	OK	
S1.006	S9	SURCHARGED	
S1.007	S10	SURCHARGED	
S1.008	S11	SURCHARGED	
S1.009	S12	SURCHARGED	
S4.000	S13	OK	
S4.001	S14	SURCHARGED	
S5.000	S15	OK	
S5.001	S16	SURCHARGED	


Malachy Walsh & Partners		Page 23
Mahon Technology Park Blackrock Cork		
Date 29/08/2023 10:48	Designed by smoriarty	
File Cloonmore drainage Stor...	Checked by	
XP Solutions		Network 2020.1.3

100 year Return Period Summary of Critical Results by Maximum Level (Rank 1) for Storm

PN	US/MH Name	Storm	Return Period	Climate Change	First (X) SurchARGE	First (Y) Flood	First (Z) Overflow
S1.010	S17	10080 Winter	100	+20%	30/7200 Winter	100/8640 Summer	
S6.000	S18	15 Winter	100	+20%			
S6.001	S19	15 Winter	100	+20%			
S6.002	S20	15 Winter	100	+20%			
S6.003	S21	15 Winter	100	+20%			
S6.004	S22	15 Winter	100	+20%			
S6.005	S23	10080 Winter	100	+20%	100/5760 Winter		
S1.011	S24	10080 Winter	100	+20%	30/4320 Winter		
S1.012	S25	10080 Winter	100	+20%	30/2160 Winter		
S1.013	S26	8640 Winter	100	+20%	1/10080 Winter		
S1.014	S27	10080 Winter	100	+20%			
S7.000	S28	10080 Winter	100	+20%	30/4320 Winter		
S7.001	S29	10080 Winter	100	+20%	1/2880 Winter		
S7.002	S30	10080 Winter	100	+20%			


PN	US/MH Name	Overflow Act.	Water Level (m)	Surcharged Depth (m)	Flooded Volume (m³)	Flow / Cap. (l/s)	Half Drain Time (mins)	Pipe Flow (l/s)
S1.010	S17		6.559	0.376	0.000	0.07		7.0
S6.000	S18		6.635	-0.137	0.000	0.55		32.5
S6.001	S19		6.568	-0.083	0.000	0.74		42.5
S6.002	S20		6.523	-0.038	0.000	0.81		40.9
S6.003	S21		6.496	-0.029	0.000	0.99		55.7
S6.004	S22		6.432	-0.015	0.000	0.96		55.0
S6.005	S23		6.394	0.036	0.000	0.02		1.1
S1.011	S24		6.393	0.284	0.000	0.07		7.2
S1.012	S25		6.430	0.435	0.000	0.07		7.3
S1.013	S26		6.430	0.449	0.000	0.06		7.5
S1.014	S27		6.409	-0.941	0.000	0.00		0.0
S7.000	S28		7.446	0.346	0.000	0.01		1.0
S7.001	S29		7.446	0.664	0.000	0.02		1.0
S7.002	S30		7.446	-0.204	0.000	0.00		0.0

PN	US/MH Name	Status	Level Exceeded
S1.010	S17	SURCHARGED	
S6.000	S18	OK	
S6.001	S19	OK	
S6.002	S20	OK	
S6.003	S21	OK	
S6.004	S22	OK	
S6.005	S23	SURCHARGED	
S1.011	S24	SURCHARGED	

Malachy Walsh & Partners		Page 24
Mahon Technology Park Blackrock Cork		
Date 29/08/2023 10:48	Designed by smoriarty	
File Cloonmore drainage Stor...	Checked by	
XP Solutions	Network 2020.1.3	
<u>100 year Return Period Summary of Critical Results by Maximum Level (Rank 1) for Storm</u>		
	</	

Appendix F

Foul Water Design Report

Malachy Walsh & Partners		Page 1
Mahon Technology Park Blackrock Cork		
Date 29/08/2023 09:39 File Cloonmore drainage Foul...	Designed by smoriarty Checked by	
XP Solutions	Network 2020.1.3	

FOUL SEWERAGE DESIGN











Design Criteria for Foul - Main

Pipe Sizes STANDARD Manhole Sizes STANDARD

Industrial Flow (l/s/ha)	0.00	Add Flow / Climate Change (%)	0
Industrial Peak Flow Factor	0.00	Minimum Backdrop Height (m)	0.200
Flow Per Person (l/per/day)	150.00	Maximum Backdrop Height (m)	1.500
Persons per House	3.00	Min Design Depth for Optimisation (m)	1.200
Domestic (l/s/ha)	0.00	Min Vel for Auto Design only (m/s)	0.75
Domestic Peak Flow Factor	6.00	Min Slope for Optimisation (1:X)	500


Designed with Level Soffits

Network Design Table for Foul - Main

PN	Length (m)	Fall (m)	Slope (1:X)	Area (ha)	Houses	Base Flow (l/s)	k (mm)	HYD SECT	DIA (mm)	Section Type	Auto Design
F1.000	42.125	0.211	199.6	0.000	32	0.0	1.500	o	225	Pipe/Conduit	
F1.001	45.471	0.227	200.3	0.000	1	0.0	1.500	o	225	Pipe/Conduit	
F1.002	19.784	0.099	199.8	0.000	0	0.0	1.500	o	225	Pipe/Conduit	
F2.000	50.189	0.251	200.0	0.000	31	0.0	1.500	o	225	Pipe/Conduit	
F3.000	69.966	0.350	199.9	0.000	82	0.0	1.500	o	225	Pipe/Conduit	
F3.001	23.341	0.117	199.5	0.000	0	0.0	1.500	o	225	Pipe/Conduit	
F3.002	16.477	0.082	200.9	0.000	1	0.0	1.500	o	225	Pipe/Conduit	
F3.003	12.428	0.062	200.5	0.000	0	0.0	1.500	o	225	Pipe/Conduit	
F3.004	12.453	0.062	200.9	0.000	0	0.0	1.500	o	225	Pipe/Conduit	
F1.003	2.524	0.013	194.2	0.000	0	0.0	1.500	o	225	Pipe/Conduit	

Network Results Table


PN	US/IL (m)	Σ Area (ha)	Σ Base Flow (l/s)	Σ Hse	Add Flow (l/s)	P.Dep (mm)	P.Vel (m/s)	Vel (m/s)	Cap (l/s)	Flow (l/s)
F1.000	6.050	0.000	0.0	32	0.0	27	0.36	0.81	32.2	1.0
F1.001	5.839	0.000	0.0	33	0.0	28	0.36	0.81	32.2	1.0
F1.002	5.612	0.000	0.0	33	0.0	28	0.37	0.81	32.2	1.0
F2.000	6.150	0.000	0.0	31	0.0	27	0.36	0.81	32.2	1.0
F3.000	6.250	0.000	0.0	82	0.0	43	0.48	0.81	32.2	2.6
F3.001	5.900	0.000	0.0	82	0.0	43	0.48	0.81	32.3	2.6
F3.002	5.783	0.000	0.0	83	0.0	43	0.48	0.81	32.1	2.6
F3.003	5.701	0.000	0.0	83	0.0	43	0.48	0.81	32.2	2.6
F3.004	5.639	0.000	0.0	83	0.0	43	0.48	0.81	32.1	2.6
F1.003	5.513	0.000	0.0	147	0.0	57	0.58	0.82	32.7	4.6


Malachy Walsh & Partners		Page 2
Mahon Technology Park Blackrock Cork		
Date 29/08/2023 09:39	Designed by smoriarty	
File Cloonmore drainage Foul...	Checked by	
XP Solutions		Network 2020.1.3

Manhole Schedules for Foul - Main


MH Name	MH CL (m)	MH Depth (m)	MH Connection	MH Diam., L*W (mm)	PN	Pipe Out Invert Level (m)	Diameter (mm)	PN	Pipes In Invert Level (m)	Diameter (mm)	Backdrop (mm)
F1	7.584	1.534	Open Manhole	1200	F1.000	6.050	225				
F2	7.529	1.690	Open Manhole	1200	F1.001	5.839	225	F1.000	5.839	225	
F3	7.393	1.781	Open Manhole	1200	F1.002	5.612	225	F1.001	5.612	225	
F4	7.753	1.603	Open Manhole	1200	F2.000	6.150	225				
F5	7.762	1.512	Open Manhole	1200	F3.000	6.250	225				
F6	7.390	1.490	Open Manhole	1200	F3.001	5.900	225	F3.000	5.900	225	
F7	7.275	1.492	Open Manhole	1200	F3.002	5.783	225	F3.001	5.783	225	
F8	7.302	1.601	Open Manhole	1200	F3.003	5.701	225	F3.002	5.701	225	
F9	7.418	1.779	Open Manhole	1200	F3.004	5.639	225	F3.003	5.639	225	
F4	7.523	2.010	Open Manhole	1200	F1.003	5.513	225	F1.002	5.513	225	
								F2.000	5.899	225	386
								F3.004	5.577	225	64
F	7.486	1.986	Open Manhole	0		OUTFALL		F1.003	5.500	225	


MH Name	Manhole Easting (m)	Manhole Northing (m)	Intersection Easting (m)	Intersection Northing (m)	Manhole Access	Layout (North)
F1	484557.081	614338.662	484557.081	614338.662	Required	
F2	484517.000	614325.701	484517.000	614325.701	Required	
F3	484528.802	614281.789	484528.802	614281.789	Required	
F4	484576.795	614277.313	484576.795	614277.313	Required	
F5	484610.084	614221.969	484610.084	614221.969	Required	
F6	484543.542	614200.348	484543.542	614200.348	Required	
F7	484537.258	614222.827	484537.258	614222.827	Required	
F8	484529.840	614237.540	484529.840	614237.540	Required	



Malachy Walsh & Partners		Page 3
Mahon Technology Park Blackrock Cork		
Date 29/08/2023 09:39 File Cloonmore drainage Foul...	Designed by smoriarty Checked by	
XP Solutions	Network 2020.1.3	

Manhole Schedules for Foul - Main

MH Name	Manhole Easting (m)	Manhole Northing (m)	Intersection Easting (m)	Intersection Northing (m)	Manhole Access	Layout (North)
F9	484527.197	614249.683	484527.197	614249.683	Required	
F4	484528.997	614262.006	484528.997	614262.006	Required	
F	484526.516	614261.544			No Entry	

Malachy Walsh & Partners		Page 4
Mahon Technology Park Blackrock Cork		
Date 29/08/2023 09:39	Designed by smoriarty	
File Cloonmore drainage Foul...	Checked by	
XP Solutions		Network 2020.1.3

PIPELINE SCHEDULES for Foul - Main

Upstream Manhole

PN	Hyd Sect	Diam (mm)	MH Name	C.Level (m)	I.Level (m)	D.Depth (m)	MH Connection	MH DIAM., L*W (mm)
F1.000	o	225	F1	7.584	6.050	1.309	Open Manhole	1200
F1.001	o	225	F2	7.529	5.839	1.465	Open Manhole	1200
F1.002	o	225	F3	7.393	5.612	1.556	Open Manhole	1200
F2.000	o	225	F4	7.753	6.150	1.378	Open Manhole	1200
F3.000	o	225	F5	7.762	6.250	1.287	Open Manhole	1200
F3.001	o	225	F6	7.390	5.900	1.265	Open Manhole	1200
F3.002	o	225	F7	7.275	5.783	1.267	Open Manhole	1200
F3.003	o	225	F8	7.302	5.701	1.376	Open Manhole	1200
F3.004	o	225	F9	7.418	5.639	1.554	Open Manhole	1200
F1.003	o	225	F4	7.523	5.513	1.785	Open Manhole	1200

Downstream Manhole

PN	Length (m)	Slope (1:X)	MH Name	C.Level (m)	I.Level (m)	D.Depth (m)	MH Connection	MH DIAM., L*W (mm)
F1.000	42.125	199.6	F2	7.529	5.839	1.465	Open Manhole	1200
F1.001	45.471	200.3	F3	7.393	5.612	1.556	Open Manhole	1200
F1.002	19.784	199.8	F4	7.523	5.513	1.785	Open Manhole	1200
F2.000	50.189	200.0	F4	7.523	5.899	1.399	Open Manhole	1200
F3.000	69.966	199.9	F6	7.390	5.900	1.265	Open Manhole	1200
F3.001	23.341	199.5	F7	7.275	5.783	1.267	Open Manhole	1200
F3.002	16.477	200.9	F8	7.302	5.701	1.376	Open Manhole	1200
F3.003	12.428	200.5	F9	7.418	5.639	1.554	Open Manhole	1200
F3.004	12.453	200.9	F4	7.523	5.577	1.721	Open Manhole	1200
F1.003	2.524	194.2	F	7.486	5.500	1.761	Open Manhole	0

Free Flowing Outfall Details for Foul - Main

Outfall Pipe Number	Outfall Name	C. Level (m)	I. Level (m)	Min I. Level (m)	D,L (mm)	W (mm)
F1.003	F	7.486	5.500	0.000	0	0


Appendix G

BRE 365 Infiltration Testing

Soakaway Test

Trial Pit No: 1 Test No: 1 Date: 02/08/2023
 Length (m): 1.50 Datum height: 0.00 m agl
 Width (m): 0.95 Granular infill: None
 Depth (m): 1.60 Porosity of infill: 1 (assumed)

Elapsed time (minutes)	Water Depth (m below datum)	Elapsed time (minutes)	Water Depth (m below datum)
0	0.69	30	1.23
1	0.71	40	1.30
2	0.73	50	1.36
3	0.76	60	1.42
4	0.78	70	1.48
5	0.80	80	1.53
6	0.83		
7	0.88		
8	0.91		
9	0.92		
10	0.93		
15	1.05		
20	1.15		
25	1.19		



Start water depth for analysis (mbgl): 0.69
 75% effective depth (mbgl): 0.92 Elapsed time (mins): 9.0
 50% effective depth (mbgl): 1.15
 25% effective depth (mbgl): 1.37 Elapsed time (mins): 51.7
 Base of soakage zone (mbgl): 1.60

Volume outflow between 75% and 25% effective depth (m3): 0.641
 Mean surface area of outflow (m²): 3.63
 (side area at 50% effective depth + base area)
 Time for outflow between 75% and 25% effective depth (mins): 42.7

Soil infiltration rate (m/s):

6.9E-5

Remarks Results processed following BRE 365 (2007).

Notes:

Water depths measured below ground level

Project Cloonmore Regeneration LRD

Project No. 23824


Carried out by MWP

Figure

Soakaway Test

Trial Pit No: 2 Test No: 1 Date: 02/08/2023
 Length (m): 1.30 Datum height: 0.00 m agl
 Width (m): 0.95 Granular infill: None
 Depth (m): 1.58 Porosity of infill: 1 (assumed)

Elapsed time (minutes)	Water Depth (m below datum)	Elapsed time (minutes)	Water Depth (m below datum)
0	0.71	30	1.05
1	0.74	40	1.08
2	0.78	50	1.11
3	0.82	60	1.13
4	0.86	70	1.16
5	0.89	80	1.19
6	0.92	90	1.22
7	0.95	100	1.25
8	0.97	110	1.28
9	0.99	120	1.31
10	1.01	160	1.34
15	1.02	170	1.37
20	1.03	230	1.40
25	1.04	290	1.44



Start water depth for analysis (mbgl): 0.71
 75% effective depth (mbgl): 0.93 Elapsed time (mins): 6.3
 50% effective depth (mbgl): 1.15
 25% effective depth (mbgl): 1.36 Elapsed time (mins): 166.7
 Base of soakage zone (mbgl): 1.58

Volume outflow between 75% and 25% effective depth (m3): 0.531
 Mean surface area of outflow (m²): 3.17
 (side area at 50% effective depth + base area)
 Time for outflow between 75% and 25% effective depth (mins): 160.4

Soil infiltration rate (m/s):

1.7E-5

Remarks Results processed following BRE 365 (2007).

Notes:

Water depths measured below ground level

Project Cloonmore Regeneration LRD


Project No. 23824
 Carried out by MWP

Figure

Soakaway Test

Trial Pit No: 3 Test No: 1 Date: 02/08/2023
 Length (m): 1.40 Datum height: 0.00 m agl
 Width (m): 0.95 Granular infill: None
 Depth (m): 1.20 Porosity of infill: 1 (assumed)

Elapsed time (minutes)	Water Depth (m below datum)	Elapsed time (minutes)	Water Depth (m below datum)
0	0.70		
1	0.90		
2	1.10		
3	1.20		



Start water depth for analysis (mbgl): 0.70
 75% effective depth (mbgl): 0.83 Elapsed time (mins): 0.7
 50% effective depth (mbgl): 0.95
 25% effective depth (mbgl): 1.08 Elapsed time (mins): 1.9
 Base of soakage zone (mbgl): 1.20

Volume outflow between 75% and 25% effective depth (m3): 0.333
 Mean surface area of outflow (m²): 2.51
 (side area at 50% effective depth + base area)
 Time for outflow between 75% and 25% effective depth (mins): 1.2

Soil infiltration rate (m/s):

1.8E-3

Remarks Results processed following BRE 365 (2007).

Notes:

Water depths measured below ground level

Project Cloonmore Regeneration LRD


Project No. 23824
 Carried out by MWP

Figure

Soakaway Test

Trial Pit No: 1 Test No: 1 Date: 16/12/2019
 Length (m): 2.00 Datum height: 0.00 m agl
 Width (m): 0.30 Granular infill: None
 Depth (m): 0.90 Porosity of infill: 1 (assumed)

Elapsed time (minutes)	Water Depth (m below datum)	Elapsed time (minutes)	Water Depth (m below datum)
0	0.30	30	0.90
1	0.35	40	0.90
2	0.40	50	0.90
3	0.45	60	0.90
4	0.50	70	0.90
5	0.55	80	0.90
6	0.60	90	0.90
7	0.70	100	0.90
8	0.75	110	0.90
9	0.80	120	0.90
10	0.85	130	0.90
15	0.90	140	0.90
20	0.90	150	0.90
25	0.90	170	0.90



Start water depth for analysis (mbgl): 0.30
 75% effective depth (mbgl): 0.45 Elapsed time (mins): 3.0
 50% effective depth (mbgl): 0.60 Elapsed time (mins): 8.0
 25% effective depth (mbgl): 0.75
 Base of soakage zone (mbgl): 0.90

Volume outflow between 75% and 25% effective depth (m³): 0.180
 Mean surface area of outflow (m²): 1.98
 (side area at 50% effective depth + base area)
 Time for outflow between 75% and 25% effective depth (mins): 5.0

Soil infiltration rate (m/s):

3.0E-4

Remarks Results processed following BRE 365 (2007).

Notes:
 Water depths measured below ground level


Project Clonmore Housing
 Project No.
 Carried out for MWP

Figure
 Sheet 1 of 1

Soakaway Test

Trial Pit No: 2 Test No: 1 Date: 17/12/2019
 Length (m): 1.90 Datum height: 0.00 m agl
 Width (m): 0.30 Granular infill: None
 Depth (m): 0.60 Porosity of infill: 1 (assumed)

Elapsed time (minutes)	Water Depth (m below datum)	Elapsed time (minutes)	Water Depth (m below datum)
0	0.30	30	0.60
1	0.30	40	0.60
2	0.30	50	0.60
3	0.30	60	0.60
4	0.35	70	0.60
5	0.40	80	0.60
6	0.40	90	0.60
7	0.40	100	0.60
8	0.45	110	0.60
9	0.46	120	0.60
10	0.47	130	0.60
15	0.48	140	0.60
20	0.50	150	0.60
25	0.52	170	0.60



Start water depth for analysis (mbgl): 0.30
 75% effective depth (mbgl): 0.38 Elapsed time (mins): 4.6
 50% effective depth (mbgl): 0.45 Elapsed time (mins): 25.6
 25% effective depth (mbgl): 0.53
 Base of soakage zone (mbgl): 0.60

Volume outflow between 75% and 25% effective depth (m³): 0.086
 Mean surface area of outflow (m²): 1.23
 (side area at 50% effective depth + base area)
 Time for outflow between 75% and 25% effective depth (mins): 21.0

Soil infiltration rate (m/s):

5.5E-5

Remarks Results processed following BRE 365 (2007).

Notes:

Water depths measured below ground level

Project Clonmore Housing

Project No.
Carried out for MWP


Figure

Sheet 1 of 1

Soakaway Test

Trial Pit No: 3 Test No: 1 Date: 16/12/2019
 Length (m): 1.50 Datum height: 0.00 m agl
 Width (m): 0.30 Granular infill: None
 Depth (m): 0.60 Porosity of infill: 1 (assumed)

Elapsed time (minutes)	Water Depth (m below datum)	Elapsed time (minutes)	Water Depth (m below datum)
0	0.30	30	0.60
1	0.32	40	0.60
2	0.34	50	0.60
3	0.36	60	0.60
4	0.39	70	0.60
5	0.42	80	0.60
6	0.44	90	0.60
7	0.46	100	0.60
8	0.47	110	0.60
9	0.48	120	0.60
10	0.49	130	0.60
15	0.50	140	0.60
20	0.54	150	0.60
25	0.57	170	0.60



Start water depth for analysis (mbgl): 0.30
 75% effective depth (mbgl): 0.38 Elapsed time (mins): 3.7
 50% effective depth (mbgl): 0.45
 25% effective depth (mbgl): 0.53 Elapsed time (mins): 18.8
 Base of soakage zone (mbgl): 0.60

Volume outflow between 75% and 25% effective depth (m³): 0.068
 Mean surface area of outflow (m²): 0.99
 (side area at 50% effective depth + base area)
 Time for outflow between 75% and 25% effective depth (mins): 15.1

Soil infiltration rate (m/s):

7.5E-5

Remarks Results processed following BRE 365 (2007).


Notes:
 Water depths measured below ground level

Project Clonmore Housing
 Project No.
 Carried out for MWP


Figure
 Sheet 1 of 1

Appendix H

Proposed Public Lighting Layout






PROPOSED SIGHT DISTANCE PLAN LAYOUT
SCALE: 1:500



- NOTES:
1. ALL DRAWINGS ARE TO BE READ IN CONJUNCTION WITH ALL RELEVANT SPECIFICATIONS, BILLS OF QUANTITIES, ARCHITECTURAL SERVICES AND ENGINEERING DRAWINGS.
 2. ANY DISCREPANCIES BETWEEN THESE DOCUMENTS SHALL BE BROUGHT TO THE ATTENTION OF THE ENGINEER.
 3. ALL DIMENSIONS ARE IN MILLIMETRES, UNLESS NOTED OTHERWISE.
 4. ALL LEVELS ARE IN METRES RELATED TO ORDNANCE DATUM.
 5. DRAWINGS ARE NOT TO BE SCALED.

PUBLIC LIGHTING LEGEND:



P01	29-08-23	ISSUE FOR PLANNING		J.K.	I.B.
REV	DATE	DESCRIPTION		BY	APP
PROJECT:					
CLOONMORE REGENERATION LRD, TRALEE, Co. KERRY.					
TITLE:					
PUBLIC LIGHTING LAYOUT					
CLIENT:					
TULFARRIS CG LTD					
<div><div>MWP</div><div>ENGINEERING AND ENVIRONMENTAL CONSULTANTS</div><div>CORK TRALEE LONDON LIMERICK</div><div>mwp.ie</div></div>					
DRAWN:		CHECKED:		APPROVED:	
O.B.		J.K.		I.B.	
PROJECT NUMBER:		DATE:		SCALE @ A1:	
23824		25/08/2023		1:500	
STATUS DESCRIPTION				STATUS:	
FOR INFORMATION				S2	
DRAWING NUMBER:				REV:	
23824 - MWP - 00 - 00 - DR-E - 9001				P01	

Appendix I

EV Charging Information

BUSINESS AND FLEET EV CHARGING

PROFESSIONAL AC DOUBLE OUTLET CHARGING



Professional double outlet charging units suitable for wall or ground mounting and available for both single and three phase connection, with an output range from 3kW to 22kW
RFID card or mobile phone app access, with on-line monitoring facility for charge point management and billing purposes
Open Charge Point Protocol (OCPP) v1.6 compliant, which enables connection to open public/private charging networks.
Dynamic load balancing enables the management and sharing of available power.





DIMENSIONS (WALL UNIT)	H 570 D 180 W 320 (MM)
DIMENSIONS (PEDESTAL UNIT)	H 1200 D 200 W 300 (MM)
ENERGY METER	MID APPROVED
MAINS CONNECTION	230V TO 400V 50Hz
CHARGING OUTPUT	3kW TO 22kW AC (single/three phase)
CURRENT PROTECTION	RCD TYPE A 40A MCB TYPE B 40A
SOCKET	TYPE 2 EV SOCKETS
OPERATING TEMPERATURE	-20 DEG C TO +55 DEG C
CHARGEPOINT PROTOCOL	OCPP V1.6
STANDARDS	IEC62196-2 IEC61851 (1) (22)
PROTECTION	IP55 PROTECTED
OUTER CASING	STAINLESS STEEL CASING
COMMUNICATION	GSM GPRS INTEGRATED



Appendix J

Swept Path Analysis



DO NOT SCALE FROM THIS DRAWING. USE FIGURED DIMENSIONS IN ALL CASES.
VERIFY DIMENSIONS ON SITE AND REPORT ANY DISCREPANCIES TO THE DESIGNERS IMMEDIATELY.
THIS DRAWING TO BE READ IN CONJUNCTION WITH THE DESIGNERS SPECIFICATION.
© THIS DRAWING IS COPYRIGHT AND MAY ONLY BE REPRODUCED WITH THE DESIGNERS PERMISSION.

SWEPT PATH ANALYSIS (SPA) LEGEND

- EXTENT OF BODY OUTLINE
- EXTENT OF WHEELBASE FOOTPRINT
- EXTENT OF LOAD OUTLINE
- EXTENT OF VEHICLE OUTLINE
- EXISTING ROAD
- PROPOSED ROAD
- CONCRETE APRON



VEHICLE DETAILS:

DB32 Fire Appliance



Overall Length	8.680m
Overall Width	2.180m
Overall Body Height	3.452m
Min Body Ground Clearance	0.337m
Max Track Width	2.121m
Lock-to-lock time	6.00s
Curb to Curb Turning Radius	7.910m

Design speed 5kph for all Forward movements
Design speed 2.5kph for all Reverse movements

P01	28.08.23	ISSUED FOR INFORMATION		JH	IB
REV	DATE	DESCRIPTION		BY	APP
PROJECT:					
CLOONMORE REGENERATION LRD, TRALEE					
TITLE:					
AUTO TRACKING - FIRE APPLIANCE SHEET 1 OF 3					
CLIENT:					
TULFARRIS CG LTD					
<div><div>MWP</div><div>ENGINEERING AND ENVIRONMENTAL CONSULTANTS</div><div>CORK TRALEE LONDON LIMERICK</div><div>mwp.ie</div></div>					
DRAWN:		CHECKED:		APPROVED:	
J.H.		G.F.		I.B.	
PROJECT NUMBER:		DATE:		SCALE @ A1:	
23824		AUG.2023		1:250	
STATUS DESCRIPTION				STATUS:	
FOR INFORMATION				S2	
DRAWING NUMBER:				REV:	
23824 - MWP - 00 - 00 - DR - C - 0400				P01	



INGRESS



EGRESS

DO NOT SCALE FROM THIS DRAWING. USE FIGURED DIMENSIONS IN ALL CASES.
VERIFY DIMENSIONS ON SITE AND REPORT ANY DISCREPANCIES TO THE DESIGNERS IMMEDIATELY.
THIS DRAWING TO BE READ IN CONJUNCTION WITH THE DESIGNERS SPECIFICATION.
© THIS DRAWING IS COPYRIGHT AND MAY ONLY BE REPRODUCED WITH THE DESIGNERS PERMISSION.

SWEPT PATH ANALYSIS (SPA) LEGEND

- EXTENT OF BODY OUTLINE
- EXTENT OF WHEELBASE FOOTPRINT
- EXTENT OF LOAD OUTLINE
- EXTENT OF VEHICLE OUTLINE
- EXISTING ROAD
- PROPOSED ROAD
- CONCRETE APRON



VEHICLE DETAILS:

DB32 Fire Appliance



Overall Length	8.680m
Overall Width	2.180m
Overall Body Height	3.452m
Min Body Ground Clearance	0.337m
Max Track Width	2.121m
Lock-to-lock time	6.00s
Curb to Curb Turning Radius	7.910m
Design speed 5kph for all Forward movements	
Design speed 2.5kph for all Reverse movements	

Green line shows body
Orange line shows axle/wheels

28.08.23		ISSUED FOR INFORMATION		JH	IB
REV	DATE	DESCRIPTION		BY	APP
PROJECT:					
CLOONMORE REGENERATION LRD,TRALEE					
TITLE:					
AUTO TRACKING - FIRE APPLIANCE SHEET 2 OF 3					
CLIENT:					
TULFARRIS CG LTD					
<div><div>MWP</div><div>ENGINEERING AND ENVIRONMENTAL CONSULTANTS</div><div>CORK TRALEE LONDON LIMERICK</div><div>mwp.ie</div></div>					
DRAWN:	J.H.	CHECKED:	G.F.	APPROVED:	I.B.
PROJECT NUMBER:	23824	DATE:	AUG 2023	SCALE @ A1:	1:500
STATUS DESCRIPTION					STATUS:
FOR INFORMATION					S2
DRAWING NUMBER:					REV:
23824 - MWP - 00 - 00 - DR - C - 0401					P01



INGRESS



EGRESS

DO NOT SCALE FROM THIS DRAWING. USE FIGURED DIMENSIONS IN ALL CASES.
VERIFY DIMENSIONS ON SITE AND REPORT ANY DISCREPANCIES TO THE DESIGNERS IMMEDIATELY.
THIS DRAWING TO BE READ IN CONJUNCTION WITH THE DESIGNERS SPECIFICATION.
© THIS DRAWING IS COPYRIGHT AND MAY ONLY BE REPRODUCED WITH THE DESIGNERS PERMISSION.

SWEPT PATH ANALYSIS (SPA) LEGEND

- EXTENT OF BODY OUTLINE
- EXTENT OF WHEELBASE FOOTPRINT
- EXTENT OF LOAD OUTLINE
- EXTENT OF VEHICLE OUTLINE
- EXISTING ROAD
- PROPOSED ROAD
- CONCRETE APRON



VEHICLE DETAILS:

DB32 Fire Appliance

Overall Length	8.680m
Overall Width	2.180m
Overall Body Height	3.452m
Min Body Ground Clearance	0.337m
Max Track Width	2.121m
Lock-to-lock time	6.00s
Curb to Curb Turning Radius	7.910m
Design speed 5kph for all Forward movements	
Design speed 2.5kph for all Reverse movements	

Green line shows body
Orange line shows axle/wheels

28.08.23		ISSUED FOR INFORMATION		JH	IB
REV	DATE	DESCRIPTION		BY	APP
PROJECT:					
CLOONMORE REGENERATION LRD,TRALEE					
TITLE:					
AUTO TRACKING - FIRE APPLIANCE SHEET 3 OF 3					
CLIENT:					
TULFARRIS CG LTD					
<div><div>MWP</div><div>ENGINEERING AND ENVIRONMENTAL CONSULTANTS</div><div>CORK TRALEE LONDON LIMERICK</div><div>mwp.ie</div></div>					
DRAWN:		CHECKED:		APPROVED:	
J.H.		G.F.		I.B.	
PROJECT NUMBER:		DATE:		SCALE @ A1:	
23824		AUG.2023		1:500	
STATUS DESCRIPTION				STATUS:	
FOR INFORMATION				S2	
DRAWING NUMBER:				REV:	
23824 - MWP - 00 - 00 - DR - C - 0402				P01	



DO NOT SCALE FROM THIS DRAWING. USE FIGURED DIMENSIONS IN ALL CASES.
VERIFY DIMENSIONS ON SITE AND REPORT ANY DISCREPANCIES TO THE DESIGNERS IMMEDIATELY.
THIS DRAWING TO BE READ IN CONJUNCTION WITH THE DESIGNERS SPECIFICATION.
© THIS DRAWING IS COPYRIGHT AND MAY ONLY BE REPRODUCED WITH THE DESIGNERS PERMISSION.

SWEPT PATH ANALYSIS (SPA) LEGEND



- EXTENT OF BODY OUTLINE
- EXTENT OF WHEELBASE FOOTPRINT
- EXTENT OF LOAD OUTLINE
- EXTENT OF VEHICLE OUTLINE
- EXISTING ROAD
- PROPOSED ROAD
- CONCRETE APRON

VEHICLE DETAILS:



Green line shows body
Orange line shows axle/wheels

DB32 Refuse Vehicle
Overall Length 7.900m
Overall Width 2.400m
Overall Body Height 3.183m
Min Body Ground Clearance 0.388m
Max Track Width 2.400m
Lock-to-lock time 6.00s
Curb to Curb Turning Radius 9.625m
Design speed 5kph for all Forward movements
Design speed 2.5kph for all Reverse movements

P01	28.08.23	ISSUED FOR INFORMATION		J.H	I.B
REV	DATE	DESCRIPTION		BY	APP
PROJECT:					
CLOONMORE DEVELOPMENT, TRALEE					
TITLE:					
AUTO TRACKING - REFUSE VEHICLE SHEET 1 OF 3					
CLIENT:					
TULFARRIS CG LTD					
<div><div>MWP</div><div>ENGINEERING AND ENVIRONMENTAL CONSULTANTS</div><div>CORK TRALEE LONDON LIMERICK</div><div>mwp.ie</div></div>					
DRAWN:	J.H.	CHECKED:	G.F.	APPROVED:	I.B.
PROJECT NUMBER:	23824	DATE:	AUG.2023	SCALE @ A1:	1:250
STATUS DESCRIPTION				STATUS:	
FOR INFORMATION				S2	
DRAWING NUMBER:				REV:	
23824 - MWP - 00 - 00 - DR-C-0403				P01	



INGRESS



EGRESS

DO NOT SCALE FROM THIS DRAWING. USE FIGURED DIMENSIONS IN ALL CASES.
VERIFY DIMENSIONS ON SITE AND REPORT ANY DISCREPANCIES TO THE DESIGNERS IMMEDIATELY.
THIS DRAWING TO BE READ IN CONJUNCTION WITH THE DESIGNERS SPECIFICATION.
© THIS DRAWING IS COPYRIGHT AND MAY ONLY BE REPRODUCED WITH THE DESIGNERS PERMISSION.

SWEPT PATH ANALYSIS (SPA) LEGEND



- EXTENT OF BODY OUTLINE
- EXTENT OF WHEELBASE FOOTPRINT
- EXTENT OF LOAD OUTLINE
- EXTENT OF VEHICLE OUTLINE
- EXISTING ROAD
- PROPOSED ROAD
- CONCRETE APRON

VEHICLE DETAILS:



Green line shows body
Orange line shows axle/wheels

DB32 Refuse Vehicle
Overall Length 7.900m
Overall Width 2.400m
Overall Body Height 3.183m
Min Body Ground Clearance 0.388m
Max Track Width 2.400m
Lock-to-lock time 6.00s
Curb to Curb Turning Radius 9.625m
Design speed 5kph for all Forward movements
Design speed 2.5kph for all Reverse movements

28.08.23		ISSUED FOR INFORMATION		JH	IB
REV	DATE	DESCRIPTION			BY
PROJECT: CLOONMORE DEVELOPMENT, TRALEE					
TITLE: AUTO TRACKING - REFUSE VEHICLE SHEET 2 OF 3					
CLIENT: TULFARRIS CG LTD					
<div><div>MWP</div><div>ENGINEERING AND ENVIRONMENTAL CONSULTANTS</div><div>CORK TRALEE LONDON LIMERICK</div><div>mwp.ie</div></div>					
DRAWN: J.H.		CHECKED: G.F.		APPROVED: I.B.	
PROJECT NUMBER: 23824		DATE: AUG.2023		SCALE @ A1: 1:500	
STATUS DESCRIPTION: FOR INFORMATION				STATUS: S2	
DRAWING NUMBER: 23824 - MWP - 00 - 00 - DR-C-0404				REV: P01	



INGRESS



EGRESS

DO NOT SCALE FROM THIS DRAWING. USE FIGURED DIMENSIONS IN ALL CASES.
VERIFY DIMENSIONS ON SITE AND REPORT ANY DISCREPANCIES TO THE DESIGNERS IMMEDIATELY.
THIS DRAWING TO BE READ IN CONJUNCTION WITH THE DESIGNERS SPECIFICATION.
© THIS DRAWING IS COPYRIGHT AND MAY ONLY BE REPRODUCED WITH THE DESIGNERS PERMISSION.

SWEPT PATH ANALYSIS (SPA) LEGEND

- EXTENT OF BODY OUTLINE
- EXTENT OF WHEELBASE FOOTPRINT
- EXTENT OF LOAD OUTLINE
- EXTENT OF VEHICLE OUTLINE
- EXISTING ROAD
- PROPOSED ROAD
- CONCRETE APRON

VEHICLE DETAILS:

Green line shows body
Orange line shows axle/wheels

DB32 Refuse Vehicle
Overall Length 7.900m
Overall Width 2.400m
Overall Body Height 3.183m
Min Body Ground Clearance 0.388m
Max Track Width 2.400m
Lock-to-lock time 6.00s
Curb to Curb Turning Radius 9.625m
Design speed 5kph for all Forward movements
Design speed 2.5kph for all Reverse movements

28.08.23		ISSUED FOR INFORMATION		JH	IB
REV	DATE	DESCRIPTION		BY	APP
PROJECT:					
CLOONMORE DEVELOPMENT, TRALEE					
TITLE:					
AUTO TRACKING - REFUSE VEHICLE SHEET 3 OF 3					
CLIENT:					
TULFARRIS CG LTD					
<div><div>MWP</div><div>ENGINEERING AND ENVIRONMENTAL CONSULTANTS</div><div>CORK TRALEE LONDON LIMERICK</div><div>mwp.ie</div></div>					
DRAWN:		CHECKED:		APPROVED:	
J.H.		G.F.		I.B.	
PROJECT NUMBER:		DATE:		SCALE @ A1:	
23824		AUG.2023		1:500	
STATUS DESCRIPTION				STATUS:	
FOR INFORMATION				S2	
DRAWING NUMBER:				REV:	
23824 - MWP - 00 - 00 - DR - C - 0405				P01	